

16-18 MILL STREET RESIDENTIAL DEVELOPMENT

Traffic Impact Study

Prepared For: AGK Multi-Res

December 15, 2020



TABLE OF CONTENTS

1.0	INTF	RODUC	TION	1
	1.1	The E	Existing Site	1
	1.2	Propo	osed Development	1
2.0	TRA	NSPOF	RTATION CONTEXT	5
	2.1	Road	Network	5
	2.2	Trans	sit Network	5
	2.3	Pede	strian and Cycling Network	5
3.0	PAR	KING (CONSIDERATIONS	8
	3.1	Town	n Parking Requirements	8
	3.2	Propo	osed Parking Facilities	9
	3.3		parable Residential Parking By-Laws	
	3.4		ng Policies	
	3.5		sportation Demand Management	
	3.6	Parki	ng Rationale Summary	12
4.0	TRA	FFIC V	OLUME PROJECTIONS	13
	4.1	Scop	e	13
	4.2	Existi	ing Traffic Conditions	13
		4.2.1	Existing Site Trips	14
	4.3	Futur	e Background Traffic Volumes	14
		4.3.1	Background Development Growth	14
		4.3.2	Corridor Growth	15
		4.3.3	Background Traffic Volumes	15
		4.3.4	Future Background Traffic Volumes	15
	4.4	Site 7	Traffic Forecasts	
		4.4.1	Vehicle Trip Generation	15
		4.4.2	Vehicle Trip Distribution	16
		4.4.3	Site Traffic Volumes	16
	4.5	Futur	e Total Traffic Volumes	16
5.0	OPE	RATIO	NAL ANALYSIS	22
3.0	5.1		ysis Methodology	
	5.2	-	ysis and Assumptions and Parameters	
	5.3		ations	
		5.3.1	Signalized Intersection	
		5.3.2	Unsignalized Intersections	24



6.0 CON	ICLUSIONS	25
	LIST OF TABLES	
Table 1	Town of Halton Hills Zoning By-Law 2010-0050 Car Parking Requirements	ε
Table 2	Proposed Parking Provisions – By Unit Type	ç
Table 3	Proposed TDM Implementation Plan / TDM Checklist	12
Table 4	Existing Traffic Data Sources	13
Table 5	Area Background Development	14
Table 6	Background Development Trip Generation	14
Table 7	Site Vehicle Trip Generation	15
Table 8	Site Traffic Distribution	16
Table 9	Peak Hour Analysis Results: Guelph St / Mill St	23
Table 10	95 th Percentile Queues: Guelph St / Mill St	23
Table 11	Peak Hour Analysis Results: Mill St / Dayfoot Dr	24
	LIST OF FIGURES	
Figure 1:	Site Location	2
Figure 2:	Site Context	3
Figure 3:	Site Plan	
Figure 4:	Existing Lane Configuration	7
Figure 5:	Existing Traffic Volumes	17
Figure 6:	Background Traffic Volumes	18
Figure 7:	Future Background Traffic Volumes	19
Figure 8:	Site Traffic Volumes	20
Figure 9:	Future Total Traffic Volumes	21
	TABLE OF APPENDICES	
APPENDIX A	: Architectural Plans	



APPENDIX B: Turning Movement Counts

APPENDIX C: Corridor Growth Analysis

APPENDIX D: Synchro Outputs

1.0 INTRODUCTION

BA Group is retained by AGK Multi-Res to provide a traffic impact study for the Official Plan Amendment and Zoning By-law Amendment at 16-18 Mill Street in Georgetown (Halton Hills) in Halton Region. The proposed development consists of a 52-unit apartment building with 6 stories and 2 parking levels

1.1 THE EXISTING SITE

16 and 18 Mill Street are located on the northwest side of Mill Street between Guelph Street and McNabb Street. The site is bounded by residential property on the southwest and northwest, and by greenspace and Silver Creek on the northeast.

The site location and context are shown in Figure 1 and Figure 2, respectively.

The site is currently occupied by a 9-unit low-rise residential apartment building at 16 Mill Street and a triplex dwelling at 18 Mill Street. Each building is served by an access driveway. A parking lot wraps around the perimeter of the site. A sidewalk on the northwest side of Mill Street provides connections for pedestrians along the site boundary.

The Georgetown GO Station is located approximately 500 metre walking distance northeast of the site. Georgetown GO is designate an existing Major Transit Station in the Region Official Plan (ROP, Maps 1 and 3) and the Town has identified the GO station area at the top of its hierarchy of intensification areas.

The site is designated by the Official Plan (OP) and the Georgetown GO Station Area Secondary Plan as a Medium Density Residential Area and Greenlands. Under Zoning By-law 2010-0050, the site is zoned as Low Density Residential One.

The site is located within the Mill Street Corridor Precinct that is currently undergoing a neighbourhood study to identify opportunities for pedestrian, cyclist and road network improvements.

1.2 PROPOSED DEVELOPMENT

The proposed development consists of a 52-unit apartment building with 6 stories and 2 parking levels. The existing buildings on-site will be demolished to accommodate the proposed apartment building.

A total of 70 parking spaces are proposed for the site, 18 spaces at-grade and 26 spaces on each parking level. Five barrier free spaces will be provided on the site.

The proposed overall parking provision requires an amendment from the in-force Zoning By-law 2010-0050 from 91 parking spaces to 70 parking spaces.

The proposed site driveway is located at the existing driveway for 18 Mill Street and provides vehicle access to the site parking and loading areas from Mill Street.

Through pre-consultation, a road widening of up to 5.0 metres was identified by Town staff along Mill Street which has been identified on the current site plan. The site plan is shown in **Figure 3** and **Appendix A**.







FIGURE 1 SITE LOCATION



2.0 TRANSPORTATION CONTEXT

2.1 **ROAD NETWORK**

Mill Street is a local two-lane road, aligned in the northeast-southwest direction. Mill Street extends from Charles Street in the south to McNabb St in the north.

Dayfoot Drive is a local two-lane road stretching from Mill Street to a cul-de-sac adjacent to Guelph Street. The intersection with Mill Street is a three-legged intersection with stop control on Dayfoot Drive.

Guelph Street (Hwy 7) is a major east-west road that connects Georgetown to Acton in the west and Brampton in the east. The Guelph Street & Mill Street intersection is signalized with pedestrian crossings on all four legs. Left turn lanes are provided for both directions on Guelph Street, in addition to a right turn channel to Mill Street on the westbound approach.

The site is located within the Mill Street Corridor Precinct that is currently undergoing a neighbourhood study to identify opportunities for pedestrian, cyclist and road network improvements. Through pre-consultation, a road widening of up to 5.0 metres was identified by Town staff along Mill Street which has been identified on the current site plan.

The existing lane configurations for the road network are shown in **Figure 4**.

2.2 TRANSIT NETWORK

The site is well served by the Georgetown GO station that is located within a 500 metre walking distance, providing frequent access Toronto and the GTA via the Kitchener GO line.

Guelph Street is served by GO bus routes 31 and 33, including the Guelph St @ Mill St stop located 100 m east of the intersection and a 400 m walk from the site.

There is no formal provision of local transit services in the vicinity of the site.

2.3 PEDESTRIAN AND CYCLING NETWORK

Sidewalks extend along Mill Street on both sides from Charles Street to Dayfoot Drive, where the east sidewalk ends and the west sidewalk continues onward to McNabb Street.

Sidewalks are provided on both sides of Guelph Street, with pedestrian crossing signals at the Mill Street intersection.

The site is located within the Mill Street Corridor Precinct that is currently undergoing a neighbourhood study to identify opportunities for pedestrian, cyclist and road network improvements.



The Halton Hills Active Transportation Master Plan (ATMP) was endorsed by Council on October 26, 2020 further identifies improvements to the active transportation network, including:

- a proposed On-Road Facility in the form of a Signed Bike Route with Sharrows along Mill Street. The ATMP identifies this facilities for Short Term (0-5 years) implementation
- a proposed Off-Road Facility along Silver Creek. The ATMP identifies this facilities for Long Term (10+ years) implementation.

Through pre-consultation, a road widening of up to 5.0 metres was identified by Town staff along Mill Street which has been identified on the current site plan.

3.0 PARKING CONSIDERATIONS

3.1 TOWN PARKING REQUIREMENTS

The Town of Halton Hills Zoning By-law 2010-0050 requires a vehicle parking supply rate of 1.5 residential spaces plus 0.25 visitor spaces for apartment dwelling units. The summary of required spaces, as applied to the current site statistics, is shown in **Table 1**.

TABLE 1 TOWN OF HALTON HILLS ZONING BY-LAW 2010-0050 CAR PARKING REQUIREMENTS

Use	Dwelling Units	Rate	Parking Spaces Required
Residential Spaces	52	1.5 spaces/unit	78 spaces
Visitor Spaces	52	0.25 spaces/unit	13 spaces
Total Required		1.75 spaces/unit	91 spaces

Notes:

Bicycle parking is not required for residential land uses under Zoning By-law 2010-0050. The by-law also does not specify minimum requirements for barrier free vehicle parking spaces.

The Accessibility for Ontarians with Disabilities Act (AODA) requires 3 parking spaces be provided as barrier free.

^{1.} Per Zoning By-Law 2010-0050 5.3.3 Where the minimum number of parking spaces is calculated on the basis of a rate or ratio, the required number of parking spaces shall be rounded to the next higher whole number.

3.2 PROPOSED PARKING FACILITIES

The site is proposed to accommodate a total of 70 parking spaces, including 5 barrier free spaces.

This parking provision requires a variance from the zoning bylaw as the proposed provision of spaces is lower than the required rate.

The proposed vehicular parking rates for the current application are:

- 1.10 spaces per unit for residents¹
- 0.25 spaces per unit for visitors

This is equivalent to effectively providing 1.00 spaces per one-bed unit and 1.2 spaces per two-bed units. A summary of the proposed parking, by rate and unit type, is outlined in **Table 2**.

A rate of 0.25 spaces per unit is provided for visitors, consistent with the Halton Hills bylaw.

TABLE 2 PROPOSED PARKING PROVISIONS - BY UNIT TYPE

Use	Dwelling Units	Rate	Parking Spaces Provided
Residential Spaces	26 one-bed units 26 two-bed units	1.00 space per one-bed unit 1.20 spaces per two-bed unit	26 spaces 31 spaces ¹ 57 res. spaces (1.1 sps/unit)
Visitor Spaces	52 total units	0.25 spaces per unit	13 visitor spaces
Total		1.35 space per unit	70 total spaces ¹

Notes:

The resident parking supply is 21 spaces less than the zoning bylaw requirements of 91 spaces.

The site parking provisions meet the zoning bylaw requirements for visitor parking



For the purpose of calculating proposed parking by unit type, the number of parking spaces for two-bed units (31.2) was rounded down.


¹ For the purpose of calculating proposed parking by unit type, the number of parking spaces was rounded down.

3.3 COMPARABLE RESIDENTIAL PARKING BY-LAWS

BA Group reviewed parking rates from a number of municipalities where there is a comparable proximity to regional transit and active transportation, including proximity to a GO station, GO transit service distance to Union Station and/or frequencies similar to that of Georgetown GO along the Kitchener GO line. The Halton Hills zoning bylaw, site proposed parking variance and comparable bylaws are presented in the graph below.

Some of zoning bylaws reviewed identify rates for one-bed, two-bed, and three-bed dwelling types while others have a rate for all apartment dwelling units, regardless of unit type. For the purpose of providing a direct comparison, each bylaw rate has been presented as it would apply to the proposed 16-18 Mill development statistics for 26 one-bed units and 26 two-bed units.

Both Barrie and St. Catharines provide a combined required resident and visitor parking rate that includes an undefined number of visitor spaces. Visitor parking rates typically range between 0.10 and 0.25 spaces per unit across Ontario municipal bylaws for apartment dwelling units. A dashed line is represented in the graph for both Barrie and St. Catharines, to identify approximate resident parking allocation requirements.



The existing Halton Hills parking requirement of 1.5 resident spaces per unit exceeds the required rates observed in comparable municipalities. The resident parking requirements for apartment uses in Halton Hills do not differ based on location, unit type, or proximity to transit and active transportation.

The proposed parking requirement for 16-18 Mill Street represents a comparable requirement to the municipalities presented in the graph above and is representative of a parking supply in a transit oriented neighbourhood that is undergoing intensification. The effective rate for 16-18 Mill Street of 1.10 also reflects a representative rate for unit type mix, that supplies parking at a rate of 1.0 spaces per one-bed unit and 1.2 spaces per two-bed unit, respectively, for the site.



3.4 PARKING POLICIES

The Halton Region Official Plan (ROP) includes the following policies that are supportive area specific parking standards related to Major Transit Station Areas and Intensification Areas:

ROP Policy 81 (8) Encourage the Local Municipalities to adopt parking standards and policies within Intensification Areas to promote the use of active transportation and public transit.

ROP Policy 173 (21) e) Require the Local Municipality to adopt parking policies in the Intensification Areas that would promote active transportation and the use of public transit.

The Town of Halton Hills Official Plan (OP) includes the following policies that are supportive of active transportation and parking standards specific to the Georgetown Station Secondary Plan:

OP Policy F6.7 The Town shall review off-street and on-street parking regulations to reflect evolving patterns of automobile use at the time of the preparation of the implementing Zoning By-law. Reduced parking requirements may be considered where sufficient public off-street and on-street parking facilities exist. In addition, parking requirements may be reduced if the uses on the lot each require parking at different times of the day. Opportunities for the sharing of parking in mixed use development will be considered during the review of a development application.

3.5 TRANSPORTATION DEMAND MANAGEMENT

Transportation Demand Management (TDM) strategies encompass a range of policies, tools, and programs designed to promote and facilitate the use of walking, cycling, public transit, telecommuting and carpooling as an alternative to single passenger vehicle travel. TDM strategies aim to reduce vehicle travel with the primary objective of:

- reducing demand on road infrastructure, thereby minimizing road and parking capital expenditures;
- increasing travel efficiency;
- reducing climate change emissions;
- · improving air quality; and,
- improving overall health.

A TDM plan has been crafted to tailor to the future residents of the 16-18 Mill Street proposed development. The components of the proposed TDM plan are outlined below.



TABLE 3 PROPOSED TDM IMPLEMENTATION PLAN / TDM CHECKLIST

	Measure	Description
1	Reduced Vehicular Parking Supply	The reduction of parking supply (compared to the applicable requirements) is itself a TDM measure as it will force residents/visitors to consider alternative travel modes.
2	"Unbundle Parking"	This measure is also inherent to the reduced parking supply; since units are rentals, a sales program should be commenced which gives renters the option of leasing a parking space.
3	Visible Transit Information	The lobby of the building should have access to local and regional transit information to assist residents in taking transit.
4	Bicycle Parking	The proposed development shall meet the bicycle parking requirements of the site specific zoning by-law to support and encourage bicycle use to and from the site. Provide short-term bicycle parking in highly visible locations in close proximity to major entrance.
5	Transit Stop	The site is located within 500 metres of the Georgetown GO regional rail service. The site is providing a 5 metre widening along Mill Street that will allow to improve the active transportation facilities within the Mill Street Corridor Precinct. These measures will improve pedestrian and active transportation facilities and will make transit use more attractive and accessible.

3.6 PARKING RATIONALE SUMMARY

The proposed resident parking supply of 1.10 spaces per unit for 16-18 Mill Street is consistent with the range of required parking rates at comparable locations across Ontario for residential uses near a Major Transit Station area or along Transit Oriented Corridors.

Parking for the site can be 'unbundled' for apartment uses. Building management can lease and manage parking leases on an ongoing basis and adopt shared (unassigned) parking for residents within a 'pool' of parking. Sharing will maximize the efficiency of the site's overall parking supply, and in turn will minimize parking supply excesses.

Resident parking is supplied at a rate of 1.0 spaces per one-bed unit and 1.2 spaces per two-bed units, ensuring a minimum of one parking space for each apartment unit – without oversupplying the amount of structured parking required to be built on site.

A rate of 0.25 spaces per unit is provided for visitors, consistent with the Halton Hills bylaw.

A bike parking rack will be provided next to the Main Entrance on Mill Street and a 5 metre widening along Mill Street will allow provision for an improved sidewalk and cycling facilities along Mill Street that will make active transportation and transit use more attractive and accessible.

4.0 TRAFFIC VOLUME PROJECTIONS

4.1 SCOPE

The study area for this site comprises of three intersections:

- Mill Street & Site Access;
- Mill Street & Dayfoot Drive;
- Mill Street & Guelph Street.

In accordance with Halton Region's TIS guidelines, a horizon period of 5 years was adopted for the future impact analysis. Traffic analysis was completed for the following scenarios during the weekday morning (AM) and afternoon (PM) peak hour:

- Existing Traffic Conditions
- 5-year Future Background Traffic Conditions (2025)
- 5-year Future Total Traffic Conditions (2025)

4.2 EXISTING TRAFFIC CONDITIONS

Existing peak hour traffic volumes at the site driveways have been established based on traffic counts provided by the Town and supplemented by counts undertaken by Spectrum Traffic Data on behalf of BA Group.

A summary of the counts undertaken is provided in **Table 4**. The corresponding turning movement counts are attached in **Appendix B**.

TABLE 4 EXISTING TRAFFIC DATA SOURCES

Intersection	Count Date	Count Times	Source
Guelph Street / Mill Street	Monday, November 5 th , 2018	7:00 AM-9:00 AM 11:00 AM-2:00 PM 3:00 PM-6:00 PM	Town
Guelph Street / Mill Street	Tuesday, November 3 rd , 2020	7:00 AM-9:00 AM	Spectrum Traffic
Mill St / Dayfoot Drive	Tuesuay, November 3", 2020	4:00 PM-6:00 PM	Data

As the counts conducted by Spectrum were completed during the COVID-19 pandemic, it is anticipated that these counts reflect reduced traffic volumes compared to normal operations. To obtain a more accurate representation of existing conditions at Mill St / Dayfoot Dr, an adjustment factor was obtained by comparing the two-way volumes on the north leg of Guelph St / Mill St during the two count dates. The through volumes on Mill St were then balanced to obtain the final adopted volumes for existing conditions.

The adopted existing baseline area traffic volumes for the weekday AM and PM peak hour are provided in **Figure 5**.



4.2.1 Existing Site Trips

To remain conservative, it was assumed that the existing trips from the site were negligible and did not warrant removal from the background traffic volumes.

4.3 FUTURE BACKGROUND TRAFFIC VOLUMES

4.3.1 Background Development Growth

Two background developments were identified by the Town within the vicinity of the site, as summarized in **Table 5**.

TABLE 5 AREA BACKGROUND DEVELOPMENT

Location	Type Development Description		Study	Status
42 Mill Street	Residential	Building 1: 6 storey condominium – 76 residential units	Report prepared	Under construction
	Residential	Building 2: 3-storey townhouses – 14 residential units	by LEA Consulting Ltd (dated November	Under review
	Residential	Building 3: 5-storey condominium – 116 residential units	2016)	Under review
22 Dayfoot Drive	Residential	5-storey condominium – 82 residential units	N/A	Pre-consultation

Although a TIS was prepared for 42 Mill Street, a review of the study indicated substantial changes in the proposed development since the TIS was written. As the submitted study is now obsolete, a new trip generation analysis was completed for the development.

Background development trip generation rates were determined using the ITE Trip Generation Manual (10th Edition). The mode split characteristics for the proposed site are captured in the ITE rates associated with the specific land use. Both of the proposed developments are categorized under Land Use Code 221 – Multifamily Housing (Mid-Rise). The total vehicle trips generated from the background developments are summarized in **Table 6**.

TABLE 6 BACKGROUND DEVELOPMENT TRIP GENERATION

	Number of	Al	/I Peak Ho	our	PM Peak Hour		
	Units	ln	Out	2 Way	In	Out	2 Way
Trip Rate Per Dwelling Unit	_	0.09	0.27	0.36	0.27	0.17	0.14
42 Mill Street – Vehicle Trips	206	20	55	75	56	36	92
22 Dayfoot Drive – Vehicle Trips	82	10	20	30	23	15	38
Total	288	30	75	105	79	51	130

4.3.2 Corridor Growth

Corridor growth rates for Mill Street and Guelph Street were estimated using seven traffic counts spanning a period between 2005 and 2018. As there was no discernible growth along either of the roads at this intersection, a growth of 0% was assumed.

The background developments identified above will contribute directly to growth not encompassed within the 0% assumption.

Detailed corridor growth analysis charts are attached in **Appendix C**.

4.3.3 Background Traffic Volumes

Background traffic volumes, inclusive of background development growth and corridor growth along Mill Street, are shown in **Figure 6**.

4.3.4 Future Background Traffic Volumes

The future background traffic volumes, determined by adding existing traffic volumes and background traffic volumes, are shown in **Figure 7**.

4.4 SITE TRAFFIC FORECASTS

4.4.1 Vehicle Trip Generation

The ITE Trip Generation Manual (10th Edition) was used to obtain a trip generation rate for the proposed development. The proposed development is categorized under Land Use Code 221 – Multifamily Housing (Mid-Rise).

Based on the rates outlined above, the traffic volumes projected to be generated by the proposed development in the AM and PM peak hours are summarized in **Table 7**.

TABLE 7 SITE VEHICLE TRIP GENERATION

	Number of	Al	M Peak Ho	our	PM Peak Hour		
	Units	In	Out	2 Way	In	Out	2 Way
Trip Rate Per Dwelling Unit	-	0.09	0.27	0.36	0.27	0.17	0.14
Vehicle Trips	52	5	15	20	15	10	25

On the basis of the above, it is estimated that the proposed development will generate in the order of 20 and 25 two-way vehicle trips during the AM and PM peak hours respectively.



4.4.2 Vehicle Trip Distribution

Site generated traffic was assigned onto the area road network based on the trip distribution percentages summarized in **Table 8.** The distribution was determined through a TTS query for existing home-based vehicle trips in the area for the weekday peak periods.

TABLE 8 SITE TRAFFIC DISTRIBUTION

Street	Direction	AM Peak PM Peak			Peak
		Inbound	Outbound	Inbound	Outbound
Cualph St	East	60%	60%	60%	60%
Guelph St	West	10%	10%	10%	10%
Mill Street	North	20%	15%	20%	15%
Mill Street	South	10%	15%	10%	15%
Total		100%	100%	100%	100%

4.4.3 Site Traffic Volumes

The projected site traffic volumes are shown in Figure 8.

4.5 FUTURE TOTAL TRAFFIC VOLUMES

Future total traffic volumes are determined by adding the future background traffic volumes and the site traffic volumes and are shown in **Figure 9**.

Date Plotted: December 9, 2020 Filename: P:\80\70\01\Graphics\CAD\Fig08-00-ST.dwg

5.0 OPERATIONAL ANALYSIS

5.1 ANALYSIS METHODOLOGY

Synchro Version 11 and the Highway Capacity Manual (HCM) methodology were used to analyze the study area intersections.

For unsignalized intersections, level of service (LOS) characterizes operational conditions for key movements in terms of average delay experienced by vehicles attempting to complete a manoeuvre through the intersection. LOS 'A' represents a good level of service with short delays, while LOS 'F' represents a poor level of service with extended delays.

For signalized intersections, the volume to capacity ratio (V/C ratio) is an indicator of the capacity utilization for the key movements in the intersection. A V/C ratio of 1.0 indicates that certain governing traffic movements through the intersection are operating at or near maximum capacity.

Detailed analysis worksheets are attached in **Appendix D**.

5.2 ANALYSIS AND ASSUMPTIONS AND PARAMETERS

Synchro analysis were performed to conform to the requirements of the Halton Region Transportation Impact Studies Guidelines (January 2015).

The existing signal timing plan for the Guelph St / Mill Street intersection was provided by the Town and applied to all analysis scenarios.

A base saturation flow of 1,900 vehicles per hour per lane and a peak hour factor of 0.92 were assumed for all streets in the study area road network. Heavy vehicle percentages were calculated based on existing traffic volume data extracted from the traffic counts utilized in this study.



5.3 OPERATIONS

5.3.1 Signalized Intersection

A summary of the traffic capacity analysis for the existing signalized Guelph Street / Mill Street intersection is provided in **Table 9** and the 95^{th} percentile queues for the intersection are shown in **Table 10**.

TABLE 9 PEAK HOUR ANALYSIS RESULTS: GUELPH ST / MILL ST

Lane Group Existing		ting	Future Ba	ckground	Future Total	
	V/C Ratio	LOS	V/C Ratio	LOS	V/C Ratio	LOS
EBL	0.05 (0.05)	A (A)	0.07 (0.08)	A (B)	0.07 (0.08)	A (A)
EBTR	0.73 (0.59)	B (B)	0.76 (0.63)	B (B)	0.78 (0.61)	B (B)
WBL	0.51 (0.56)	D (D)	0.51 (0.54)	D (C)	0.51 (0.56)	D (D)
WBTR	0.17 (0.38)	A (A)	0.19 (0.40)	A (A)	0.19 (0.40)	A (A)
NBLTR	0.28 (0.30)	C (C)	0.28 (0.35)	C (C)	0.27 (0.31)	C (C)
SBLTR	0.22 (0.18)	C (C)	0.69 (0.52)	D (C)	0.75 (0.52)	D (C)
Overall	0.65 (0.54)	B (B)	0.75 (0.60)	B (B)	0.77 (0.60)	B (B)

Notes:

1. xx (xx) – AM Peak (PM Peak)

TABLE 10 95TH PERCENTILE QUEUES: GUELPH ST / MILL ST

Lane Group	Existing Traffic	Future Background Traffic	Future Total Traffic
EBL	1.5 (1.0)	2.1 (1.6)	2.3 (1.6)
EBTR	81.4 (56.0)	92.6 (62.2)	97.7 (60.2)
WBL	9.0 (18.5)	9.0 (18.4)	9.0 (18.5)
WBTR	6.5 (22.5)	8.6 (24.3)	9.5 (22.6)
NBLTR	6.3 (8.1)	6.8 (9.9)	6.6 (9.3)
SBLTR	7.2 (6.4)	18.5 (14.5)	21.4 (16.5)

Notes:

1. xx (xx) – AM Peak (PM Peak)

5.3.2 Unsignalized Intersections

A summary of the traffic capacity analysis for the unsignalized intersections is provided in **Table 11**.

TABLE 11 PEAK HOUR ANALYSIS RESULTS: MILL ST / DAYFOOT DR

Lane Group	Exis	ting	Future Ba	ckground	Future	: Total
	Delay (s)	LOS	Delay (s)	LOS	Delay (s)	LOS
Mill Street / Dayfoot Drive						
EBLR	8.9 (9.2)	A (A)	9.1 (9.5)	A (A)	9.2 (9.6)	A (A)
NBLT	0.6 (1.3)	A (A)	1.8 (3.3)	A (A)	1.7 (3.0)	A (A)
Mill Street / Site Access						
EBLR	()	()	()	()	8.7 (8.8)	A (A)
NBLT	()	()	()	()	0.4 (1.0)	A (A)

Notes:

Traffic operations are considered acceptable under both existing and future scenarios, considering the addition of area background traffic and site traffic. Existing and future queuing at Guelph Street / Mill Street can also be readily accommodated within the existing area road network and turning lane storage.

^{1.} xx (xx) – AM Peak (PM Peak)

6.0 CONCLUSIONS

BA Group is retained by AGK Multi-Res GP Ltd to provide a traffic impact study for a 52 unit apartment building at 16-18 Mill Street in Georgetown (Halton Hills) located in Halton Region.

Existing Site and Transportation Context

- 1. The site is currently occupied by a 9-unit low-rise residential apartment building at 16 Mill Street and a triplex dwelling at 18 Mill Street
- 2. The Georgetown GO Station is located approximately 500 metre walking distance northeast of the site. Regional GO bus routes also operate within 500 metres of the site along Guelph Street at its intersection with Mill Street.
- 3. The site is designated by the Official Plan (OP) and the Georgetown GO Station Area Secondary Plan as a Medium Density Residential Area and Greenlands. Under Zoning By-law 2010-0050, the site is zoned as Low Density Residential One.
- 4. The site is located within the Mill Street Corridor Precinct that is currently undergoing a neighbourhood study to identify opportunities for pedestrian, cyclist and road network improvements.
- 5. Through pre-consultation, a road widening of up to 5.0 metres was identified by Town staff along Mill Street which has been identified and protected for on the current site plan.
- 6. The Halton Hills Active Transportation Master Plan (ATMP) was endorsed by Council on October 26, 2020 further identifies improvements to the active transportation network, including a proposed On-Road Facility in the form of a Signed Bike Route with Sharrows along Mill Street and a proposed Off-Road Facility along Silver Creek.

Proposed Development

- 7. The proposed development consists of a 52-unit apartment building with 6 stories and 2 below grade parking levels
- 8. A total of 70 parking spaces are proposed for the site, 18 spaces at-grade and 26 spaces on each parking level. Five barrier free spaces will be provided on the site.
- 9. The proposed overall parking provision requires an amendment from the in-force Zoning By-law 2010-0050 from 91 parking spaces to 70 parking spaces.
- 10. The proposed site driveway is located at the existing driveway for 18 Mill Street and provides vehicle access to the site parking and loading areas from Mill Street.
- 11. A bike parking rack will be provided next to the Main Entrance on Mill Street and a 5 metre widening along Mill Street will allow provision for an improved sidewalk and cycling facilities along Mill Street that will make active transportation and transit use more attractive and accessible.



Parking Considerations

- 12. The current application proposes to vary the required vehicle parking supply for the site to provide for 70 parking spaces for 52 apartment dwelling units, of which 57 (1.1 spaces per unit) will be provided for residents and 13 (0.25 spaces per unit) will be provided for visitors.
- 13. Resident parking is effectively supplied at a rate of 1.0 spaces per one-bed unit and 1.2 spaces per two-bed units, ensuring a minimum of one parking space for each apartment unit without oversupplying the amount of structured parking required to be built on site.
- 14. Resident parking is consistent with the range of required parking rates at comparable locations across Ontario for residential uses near a similar Major Transit Station area or along Transit Oriented Corridors.
- 15. Parking for the site can be 'unbundled' for apartment uses. Building management can lease and manage parking leases on an ongoing basis and adopt shared (unassigned) parking for residents within a 'pool' of parking. Sharing will maximize the efficiency of the site's overall parking supply, and in turn will minimize parking supply excesses.
- 16. The rate of 0.25 spaces per unit provided for visitors is consistent with the Town of Halton Hills bylaw.

The proposed parking supply for the site is appropriate for the proposed apartment dwelling land use, one and two-bedroom dwelling unit types, transit and active transportation context, and TDM measures associated with not over-supplying parking on the site.

Traffic

- 17. Traffic operations have been reviewed for existing, future background, and future total conditions for existing (2020) and full buildout (2025).
- 18. Background traffic allowances were made for the proposed developments at 42 Mill Street and 22 Dayfoot Drive.
- 19. The site is estimated to generate 20 and 25 two-way vehicle trips during the morning and afternoon peak hours, respectively.

Site traffic volumes can be acceptably accommodated on the local area road network and site driveway under future background and future total conditions. No road network improvements are required to accommodate site traffic under future total conditions.

We trust the foregoing provides an appropriate presentation of our analysis, as well as a satisfactory discussion of all relevant results and their implications. Please do not hesitate to contact us directly should you require any further information and/or clarification.

BA Consulting Group Ltd.


Emily J. Ecker, P.Eng. Associate



APPENDIX A: Architectural Plans



GREENSPACE - SILVER CREEK




SI	TE DATA		
16 +	18 Mill Street, Georgetown, Ontario		
DAT	ΓA	EXISTING ZONE	PROPOSED
EXIS	TING ZONING	ZONING - LDR1-2	
PROPOSED ZONING		ZONING - HDR - SPECIAL	
LOT AREA (m²) - PRE-ROAD WIDENING		2271.69 (m²)	
LOT	AREA (m²) - POST-ROAD WIDENING	2070.5	51 (m²)
MINI	MUM LOT FRONTAGE (m)	11.0 (m)	40.23 (m)
S	FRONT YARD (m)	4.5 (m)	3.0 (m)
SETBACKS	INTERIOR SIDE YARD (m)	7.5 (m)	3.5 (m)
TB,	EXTERIOR SIDE YARD (m)	6.0 (m)	6.0 (m)
SE	REAR YARD (m)	7.5 (m)	6.0 (m)


BUILDING DATA					
DATA	REQUIRED	PROVIDED			
TOTAL DENSITY (# of units)	100 (units per ha.)	52 (units)			
BUILDING AREA (m²)	XX (m²)	848.08 (m²)			
GROSS FLOOR AREA (m²)	XX (m²)	4,366.8 (m²)			
FLOOR SPACE INDEX (FSI) INCLUDING BELOW GRADE	XX (m²)	GFA + P1 & P2 COMM. AND SERVICE/ LOT AREA = 2.24			
FLOOR SPACE INDEX (FSI) ABOVE GRADE ONLY	XX (m²)	GFA / LOT AREA = 2.11			
NUMBER OF STOREYS	6 MAX.	6			
BUILDING HEIGHT (m)	XX (m) MAX.	XX (m)			
AMENITY AREA (m²)	XX (m²)	71.50 (m²)			

LANDSCAPING DATA				
DATA	REQUIRED	PROVIDED		
LANDSCAPE AREA (percentage)	XX (%)	26.5 (%)		
LANDSCAPE AREA (m²)	XX (m²)	549.2 (m²)		

VEHICLE PARKING DATA		
DATA	REQUIRED	PROVIDED
RESIDENTIAL PARKING	1.75 / units = 93	1.32 / unit = 70
BARRIER FREE PARKING	5	5
VISITOR PARKING	0.X / units	XX
LOADING SPACE	N/A	N/A
	TOTAL	XX

BICYCLE PARKING DATA			
DATA	REQUIRED	PROVIDED	
RESIDENTIAL BICYCLE PARKING	N/A	XX	
COMMERCIAL BICYCLE PARKING	N/A	XX	
	TOTAL	XX	





EDAL NOTES

NERAL NOTES

HAVE PRECEDENCE OVER SCALED DIMENSIONS.

2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.

5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE

CONSULTANT FOR THE ACCOUNT OF THE OWNER.

6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE

CONTRACT DOCUMENTS WERE PREPARED BY THE

RESPONSIBILITY OF SUCH THIRD PARTIES.

7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.


No.	Date	Revision
'	2020-03-20	Ochsultani Goordination
1	2020-09-28	Consultant Coordination
2	2020-11-19	Consultant Coordination
3	2020-12-04	Consultant Coordination




Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MY∖
Plot Date / Time	
2020-12-0	09 1:46:19 PM

16 & 18 MILL STREET, GEORGETOWN DEVELOPMENT

SITE PLAN








AREA STATISTICS - L	EVEL P1
Name	Area

EXIT STAIR	18.35 m ²
ELEVATOR	8.31 m ²
ELEVEATOR LOBBY	15.75 m ²
EXIT STAIR	15.74 m ²
STORAGE	38.29 m ²
	96.44 m ²

Parking	
P1 PARKING LEVEL	1197.03
	1197.03

Services	
VESTIBULE	6.80 m ²
SERVICES	26.84 m ²
	33.64 m²
Grand total	1327.11 m ²

AREA STATISTICS - LEVEL P1	
Name	Area



GENERAL NOTES

1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.

ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.


CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.

RESPONSIBILITY OF SUCH THIRD PARTIES.

5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE

6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHITE OF A THIRD OF THE CONTRACT POSITIONS OF ANY PER LANGE. OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE

7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.







Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MYV
Plot Date / Time	
2020-12-0	9 1:46:19 PM

16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

P1 LEVEL PARKING





AREA STATISTICS - LEVEL P2 Name Area


Common	
EXIT STAIR	18.35 m ²
ELEVATOR	8.31 m ²
ELEVATOR LOBBY	15.75 m ²
EXIT STAIR	15.74 m²
STORAGE	38.29 m²
	96.44 m²

Parking P2 PARKING LEVEL 1197.03 m² 1197.03 m²

Services VESTIBULE 6.80 m² SERVICES 26.84 m² 33.64 m²

Grand total

1327.11 m²



GENERAL NOTES

1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.

ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.


PROHIBITED WITHOUT WRITTEN PERMISSION. THE

5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS

CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER. 6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE

RESPONSIBILITY OF SUCH THIRD PARTIES. 7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.

ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE








	20052
Project Date	2020-12-09
	2020-12-09
Drawn by	TJM
	I JIVI
Checked by	
	MYV
Plot Date / Time	
2020-12-09	9 1:46:19 PM


16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

P2 LEVEL PARKING










: North Tru

GENERAL NOTES

- 1. **DO NOT SCALE DRAWINGS**. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
- 2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.
- 3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.
- PROCEEDING WITH THE WORK.

 4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS
- ON SITE AT ALL TIMES.

 5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE
- ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.
- 6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE RESPONSIBILITY OF SUCH THIRD PARTIES.
- 7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.







Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MYV
Plot Date / Time	
2020-12-0	9 1:46:20 PM

16 & 18 MILL STREET, GEORGETOWN DEVELOPMENT

LEVEL 1 FLOOR PLAN







Common	
CORRIDOR	48.64 m²
ELEVATOR	8.31 m ²
STAIR A	15.81 m ²
STAID B	16 50 m²

LLLVAION	0.51 111
STAIR A	15.81 m ²
STAIR B	16.50 m ²
	89.26 m ²
Residential	
1 BED UNIT	57.16 m ²
1 BED UNIT	57.19 m ²
1 BED UNIT	59.30 m ²
1 BED UNIT	61.36 m ²
1 BED UNIT	61.75 m ²
1 BED UNIT	64.35 m ²
1 BED UNIT	64.35 m ²
2 BED UNIT	69.92 m ²
2 BED UNIT	71.13 m ²
2 BED UNIT	80.40 m ²

	040.90 111
Services	
ELEC. CLOSET	4.45 m ²
REFUSE CHUTE	7.19 m ²
SHAFT	1.95 m ²
	13.59 m²

STAIR B

Residential

1 BED UNIT 1 BED UNIT

1 BED UNIT

1 BED UNIT

1 BED UNIT

1 BED UNIT

1 BED UNIT

1 BED UNIT

2 BED UNIT

2 BED UNIT

2 BED UNIT

Services

SHAFT

Grand total

ELEC. CLOSET

REFUSE CHUTE

CORRIDOR	48.64 m²
ELEVATOR	8.31 m ²
STAIR A	15.81 m ²
STAIR B	16.50 m ²
	89.26 m ²
Residential	
1 BED UNIT	57.16 m ²
1 BED UNIT	57.19 m ²
1 BED UNIT	59.30 m ²
1 BED UNIT	61.36 m ²
1 BED UNIT	61.75 m ²
1 BED UNIT	64.35 m ²
1 BED UNIT	64.35 m ²
2 BED UNIT	69.92 m ²
2 BED UNIT	71.13 m ²
2 BED UNIT	80.40 m ²
	646.90 m ²
Services	
ELEC. CLOSET	4.45 m ²
REFUSE CHUTE	7.19 m ²
SHAFT	1.95 m ²
	13.59 m²
Grand total	749.76 m ²

AREA STATISTIC	S - LEVEL 3			
Name	Area	3	2020-12-04	Consultant Coordination
inallie	Alea	2	2020-11-19	Consultant Coordination
		1	2020-09-28	Consultant Coordination
Common		No.	Date	Revision
CORRIDOR	48.64 m²	140.	Date	IVEAISIOII
ELEVATOR	8.31 m²			

16.50 m²

89.26 m²

57.16 m²

57.19 m² 59.30 m²

61.36 m²

61.75 m²

64.35 m²

64.35 m²

65.01 m²

69.92 m²

71.13 m²

80.40 m²

711.92 m²

4.45 m²

7.19 m²

1.95 m² 13.59 m²

814.77 m²



Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MYV
Plot Date / Time	
2020-12-0	9 1:46:21 PM

True North

GENERAL NOTES

PROCEEDING WITH THE WORK.

ON SITE AT ALL TIMES.

CONTRACT DOCUMENTS.

1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.

2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS

CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.

6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF

RESPONSIBILITY OF SUCH THIRD PARTIES.

PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE


7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE


5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE

16 & 18 MILL STREET, **GEORGETOWN**

DEVELOPMENT

LEVEL 2-3 FLOOR PLAN





AREA STATISTICS - LEVEL 4


Name

CORRIDOR	48.64 m ²
ELEVATOR	8.31 m ²
STAIR	16.50 m ²
STAIR A	15.81 m ²
	89.26 m ²
Residential	
1 BED UNIT	56.90 m ²

Area

STAIR A	15.81 m ²
	89.26 m ²
Residential	
1 BED UNIT	56.90 m ²
1 BED UNIT	61.36 m ²
1 BED UNIT	61.75 m ²
2 BED UNIT	60.08 m ²
2 BED UNIT	67.28 m ²
2 BED UNIT	69.92 m ²
2 BED UNIT	71.13 m ²
2 BED UNIT	71.52 m ²
2 BED UNIT	80.40 m ²
	600.33 m

Services	
ELEC. CLOSET	4.45 m ²
REFUSE CHUTE	7.19 m ²
SHAFT	1.95 m ²
	13.59 m²
Grand total	703.18 m ²



True North

GENERAL NOTES

1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.

ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.

5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE

CONSULTANT FOR THE ACCOUNT OF THE OWNER. 6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE PESPONSIBILITY OF SUCH THIRD PARTIES.

RESPONSIBILITY OF SUCH THIRD PARTIES.

7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.

No.	Date	Revision
1	2020-09-28	Consultant Coordination
2	2020-11-19	Consultant Coordination
3	2020-12-04	Consultant Coordination



Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MYV
Plot Date / Time	
2020-12-0	9 1:46:22 PM

16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

LEVEL 4-5 FLOOR PLAN



A2.5 - r3






CORRIDOR	48.64 m
ELEVATOR	8.31 m ²
STAIR	16.50 m
STAIR A	15.81 m
	89.26 m

13.01 111
89.26 m ²
56.90 m ²
61.36 m ²
61.75 m ²
60.08 m ²
67.28 m ²
68.75 m ²
70.98 m ²
71.52 m ²
80.40 m ²
599.01 m

	599.01 111
Services	
ELEC. CLOSET	4.45 m ²
REFUSE CHUTE	7.19 m ²
SHAFT	2.10 m ²
	13.74 m²
Grand total	702.01 m ²



GENERAL NOTES

1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.

ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS

ON SITE AT ALL TIMES. 5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION,

AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.

6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE DESPONSIBILITY OF SUCH THIRD PAPTIES. RESPONSIBILITY OF SUCH THIRD PARTIES.

7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.


No.	Date	Revision
1	2020-09-28	Consultant Coordination
2	2020-11-19	Consultant Coordination
3	2020-12-04	Consultant Coordination




Project No	
	20052
Project Date	
	2020-12-09
Drawn by	
	TJM
Checked by	
	MYV
Plot Date / Time	
2020-12-0	9 1:46:23 PM

16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

LEVEL 6 & ROOF PLAN








GENERAL NOTES

- 1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
- 2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.

PROCEEDING WITH THE WORK.

- 3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE
- 4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS ON SITE AT ALL TIMES.
- 5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE CONSULTANT FOR THE ACCOUNT OF THE OWNER.
- 6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY DOLUMENTS OF ANY PELIANCE. OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE RESPONSIBILITY OF SUCH THIRD PARTIES.
- 7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.






Project No	
	20052
Project Date	
roject Date	2020-12-09
	2020 12 00
Orawn by	
	TJM
Checked by	
·	MYV
Plot Date / Time	
2020-12-09	1:46:28 PM

COORDINATION

16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

EAST & WEST ELEVATIONS





2 SOUTH ELEVATION
1: 125



1) NORTH ELEVATION
1: 125


GENERAL NOTES

ON SITE AT ALL TIMES.

- 1. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS.
- 2. ALL WORK SHALL COMPLY WITH THE 2012 ONTARIO BUILDING CODE AND AMENDMENTS.
- 3. CONTRACTORS MUST CHECK AND VERIFY ALL DIMENSIONS AND SPECIFICATIONS AND REPORT ANY DISCREPANCIES TO THE ARCHITECT BEFORE
- PROCEEDING WITH THE WORK. 4. ALL CONTRACTORS AND SUB-CONTRACTORS SHALL HAVE A SET OF APPROVED CONSTRUCTION DOCUMENTS
- 5. ALL DOCUMENTS REMAIN THE PROPERTY OF THE ARCHITECT. UNAUTHORIZED USE, MODIFICATION, AND/OR REPRODUCTION OF THESE DOCUMENTS IS PROHIBITED WITHOUT WRITTEN PERMISSION. THE CONTRACT DOCUMENTS WERE PREPARED BY THE

CONSULTANT FOR THE ACCOUNT OF THE OWNER.

- 6. THE MATERIAL CONTAINED HEREIN REFLECTS THE CONSULTANTS BEST JUDGEMENT IN LIGHT OF THE INFORMATION AVAILABLE TO HIM AT THE TIME OF PREPARATION. ANY USE WHICH A THIRD PARTY MAKES OF THE CONTRACT DOCUMENTS, OR ANY RELIANCE ON/OR DECISIONS TO BE MADE BASED ON THEM ARE THE RESPONSIBILITY OF SUCH THIRD PARTIES.
- 7. THE CONSULTANT ACCEPTS NO RESPONSIBILITY FOR DAMAGES, IF ANY, SUFFERED BY ANY THIRD PARTY AS A RESULT OF DECISIONS MADE OR ACTIONS BASED ON THE CONTRACT DOCUMENTS.






Project No	
	20052
	20002
Project Date	
,	2020-12-09
	2020-12-09
Drawn by	
J. a 2,	TJM
	1 3101
Checked by	
oooou 2)	MYV
	IVIYV
Plot Date / Time	
	0 4 40 07 DN
2020-12-0	9 1:46:37 PM

16 & 18 MILL STREET, **GEORGETOWN DEVELOPMENT**

NORTH & SOUTH ELEVATIONS



APPENDIX B: Turning Movement Counts



Turning Movement Count Location Name: GUELPH ST & MILL ST Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



										12	Turning M	ng Movement Count (1 . GUELPH ST & MILL ST)	1 (1 . G	UELPH	ST & M	ILL ST)										
i				N Approach MILL ST	ء				шо	E Approach GUELPH ST					S	S Approach MILL ST						W Approach GUELPH ST			Int. Total (15 min)	Int. Total (1 hr)
Start lime	Right N:W	Thru N:S	N Left Hi	U-Turn N:N	Peds N:	Approach Total	Right E:N	Thru E:W	Left E:S	U-Turn E:E	Peds E:	Approach Total	Right S:E	Thru S:N	S:W	U-Turn S:S	Peds A	Approach Total	Right W:S	Thru W:E	Left W:N	U-Turn W:W	Peds W:	Approach Total		
07:00:00	2	2	-	0	E	ω	2	43	9	0	0	51	6	0	0	0	0	6	-	103	0	0	0	104	169	
07:15:00	2	0	2	0	0	4	0	26	7	0	0	63	9	2	2	0	0	10	2	130	е е	0	2	135	212	
07:30:00	-	9	2	0	0	6	-	69	9	0	2	92	4	-	0	0	0	15	0	150	2	0	0	152	252	
07:45:00	-	6	-	0	0	1	7	63	r.	0	-	75	21	4	-	0	0	26	0	173	ιo	0	-	178	290	923
08:00:00	-	2	01	0	0	13	2	101	12	0	-	118	12	0	0	0	0	12	-	178	2	0	0	181	324	1078
08:15:00	-	8	7	0	-	16	ro.	100	15	0	4	120	28	e	2	0	4	33	0	146	2	0	-	148	317	1183
08:30:00	2	4	9	0	2	12	-	75	15	0	2	91	40	e	2	0	12	45	0	8	0	0	9	163	311	1242
08:45:00	9	ro.	7	0	-	18	9	97	19	0	0	122	40	-	0	0	7	41	-	118	е	0	0	122	303	1255
BREAK	***																								-	***************************************
16:00:00	9	က	4	0	0	13	rs.	196	21	0	-	222	56	4	23	0	0	32	-	123	е	0	-	127	394	
16:15:00	e	6	7	0	0	41	4	162	21	0	ю	187	19	7	2	0	0	28	4	159	က	0	2	166	395	
16:30:00	9	9	-	0	-	13	4	179	27	0	-	210	19	4	2	0	က	25	2	139	-	0	2	142	390	
16:45:00	4	80	е	0	7	15	2	177	24	0	е	206	56	6	2	0	0	37	4	136	0	0	0	140	398	1577
17:00:00	4	ဧ	8	0	-	10	2	202	25	0	0	232	30	9	0	0	-	36	-	111	9	0	2	118	396	1579
17:15:00	4	4	D.	0	-	13	9	176	24	0	-	206	34	9	8	0	-	43	e	113	-	0	e	117	379	1563
17:30:00	2	ဇ	4	0	0	12	3	178	22	0	0	203	28	-	-	0	2	30	4	115	-	0	3	120	365	1538
17:45:00	က	2	2	0	0	13	-	167	21	0	0	189	34	2	က	0	-	42	2	107	ις	0	2	114	358	1498
Grand Total	51	-22	63	0	10	191	09	2041	270	0	19	2371	386	26	22	0	31	464	56	2164	37	0	31	2227	5253	
Approach%	26.7%	40.3%	33%	%0			2.5%	86.1%	11.4%	%0			83.2%	12.1%	4.7%	%0			1.2%	97.2%	1.7%	%0				
Totals %	1%	1.5%	1.2%	%0		3.6%	1.1%	38.9%	5.1%	%0		45.1%	7.3%	1.1%	0.4%	%0		8.8%	0.5%	41.2%	%2.0	%0		42.4%		
Heavy	0	-	01	0			-	92	7	0			10	-	0	0		,	2	26	-	0				
Heavy %	%0	1.3%	3.2%	%0			1.7%	4.7%	2.6%	%0		,	2.6%	1.8%	%0	%0			7.7%	4.5%	2.7%	%0				
Bicycles	0	0	0	0			0	0	0	0			-	0	0	0		,	0	0	0	0				
Bicycle %	%0	%0	%0	%0			%0	%0	%0	%0			0.3%	%0	%0	%0			%0	%0	%0	%0				

Turning Movement Count Location Name: GUELPH ST & MILL ST Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



								Peak	Peak Hour: (08:00 A	08:00 AM - 09:00 AM		her: Sh	Weather: Shower Rain (4.47 °C)	in (4.4	(၁့								
Start Time			_	N Approach MILL ST	F				E A GU	E Approach GUELPH ST					S	S Approach MILL ST					W Approach GUELPH ST	oach H ST		Int. Total (15 min)
	Right	Thru	Left	U-Turn	Peds	Approach Total	Right	Thru	Left U	U-Turn	Peds Ap	Approach Total	Right	Thru	Left	U-Turn P	Peds Approa	Approach Total Right	t Thru	n Left	U-Turn	n Peds	Approach Total	
08:00:00	-	2	10	0	0	13	2	101	12	0	-	118	12	0		0	0	1 1	178	2	0	0	181	324
08:15:00	-	80	7	0	-	16	ro O	901	15	0	4	120	88	m	8	0	4	33 0	146	2	0	-	148	317
08:30:00	2	4	9	0	2	12	-	75	15	0	2	16	8	m	8	0	12	45 0	163	0	0	9	163	311
08:45:00	9	ro.	7	0	-	18	9	26	19	0	0	122	40	-	0	0	7	41 1	118	3	0	0	122	303
Grand Total	10	19	30	0	4	29	17	373	61	0	7	451	120	7	4	0	23 1:	131 2	909	2 2	0	7	614	1255
Approach%	16.9%	32.2%	20.8%	%0			3.8% 8	82.7% 13	13.5%	%0			91.6%	5.3%	3.1%	%0		- 0.3%	98.5%	% 1.1%	%0			
Totals %	0.8%	1.5%	2.4%	%0		4.7%	1.4% 2	29.7% 4	4.9%	%0		35.9%	9.6%	0.6% (0.3%	%0	10	10.4% 0.2%	, 48.2%	%9:0 %:	%0		48.9%	
PHF	0.45	0.59	0.75	0		0.82	0.71	0.92	0.8	0		0.92	0.75	0.58	0.5	0	0	_	0.85	5 0.58	0		0.85	
Heavy	 - - 	0	i - 	0	1 1 1 1	-	 	36	1 0			1 1 1 1 1 8 1	4 4 	 - -		1 0		5 0	35	- -	0 1	i 	36	
Heavy %	%0	%0	3.3%	%0		1.7%		9.7% 3		%0		8.6%	3.3%	14.3%	%0	%0	ei ei		2	-	%0		2.9%	
Lights	- - - - - - -		: : 83 :	0	1 1 1 1	82	16		20 1	0		412	116	 9	1 4	1		126	570	9	0 1	i 	578	! ! ! •
Lights %	100%	100%	%2'96	%0		98.3%	94.1% 9	90.3% 96	%2'96	%0		91.4%	%2'96	85.7% 1	100%	%0	96	96.2% 100%	, 94.2%	% 85.7%	%0		94.1%	
Single-Unit Trucks	0	0	0	0		0	0	16	-	0		17	7	0	0	0		2 0	18	-	0		19	
Single-Unit Trucks %	%0	%0	%0	%0		%0	7 %0	4.3% 1	1.6%	%0		3.8%	1.7%	%0	%0	%0	#	1.5% 0%	3%	. 14.3%	%0 '		3.1%	
Buses	0	0	-	0		-	0	10	-	0		=	2	0	0	0		2 0	13	0	0		13	
% sesng	%0	%0	3.3%	%0		1.7%	%0	2.7% 1	1.6%	%0		2.4%	1.7%	%0	%0	%0	=	1.5% 0%	2.1%	%0 %	%0		2.1%	
Articulated Trucks	0	0	0	0		0	-	10	0	0		=	0	-	0	0		1 0	4	0	0		4	
Articulated Trucks %	%0	%0	%0	%0		%0	5.9%	2.7%	%0	%0		2.4%	%0	14.3%	%0	%0	Ö	%0 %8.0	0.7%	%0 %	%0		%2'0	
Pedestrians					4	,	,			,	9	,	,	,			20			•	•	7	•	
Pedestrians%					8.6			,	,		14.6%		,	,		4	48.8%	•		•	,	17.1%		
Bicycles on Crosswalk					0	,		,	,	,	-	,	,	,			က			•	,	0	,	
Bicycles on Crosswalk%		,			%0				,		2.4%		,	,		- 7	7.3%			•	,	%0		
Bicycles on Road	0	0	0	0	0	,	0	0	0	0	0		0	0	0	0	0	0	0	0	0	0	•	

%0

%

%

%

Bicycles on Road%

Turning Movement Count Location Name: GUELPH ST & MILL ST Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



								Peak H	Peak Hour: 04:1	1:15 PM	S PM - 05:15 PM		r: Over	Weather: Overcast Clouds (5.94 °C)	nds (5	94 °C)								
Start Time				N Approach MILL ST	g. □				E.A.	E Approach GUELPH ST					้	S Approach MILL ST					W A GUI	W Approach GUELPH ST		Int. Total (15 min)
	Right	Thru	Left	U-Turn	Peds	Approach Total	Right	Thru	Left L	U-Turn F	Peds Ap	Approach Total	Right	Thru	Left U	U-Turn F	Peds Approach Total	_	Right T	Thru Le	Left U-	U-Turn Peds	Approach Total	
16:15:00	က	6	2	0	0	41	4	162	21	0	8	187	19	_	2	0	0 28	8	H	159 3	e e	0 2	166	395
16:30:00	9	9	-	0	-	13	4	179	27	0	-	210	19	4	2	0	3 25		2	139	_	0	142	390
16:45:00	4	00	е	0	2	15	2	177	24	0	е	506	56	6	2	0	0 37	7		136 0	0	0 0	140	398
17:00:00	4	e	e	0	-	10	ro.	202	25	0	0	232	98	9	0	0	1 36		-	111	9	0	118	396
Grand Total	17	56	6	0	4	52	18	720	97	0	7	835	94	56	9	0	4 12	11 11	H	545 10	10	6 0	296	1579
Approach%	32.7%	20%	17.3%	%0			2.2%	86.2% 1	11.6%	%0			74.6%	20.6% 4	4.8%	%0		1.9	1.9% 96	96.3% 1.8%		%0		
Totals %	1.1%	1.6%	%9.0	%0		3.3%	1.1%	45.6% 6	6.1%	%0		52.9%	%9	1.6% 0	0.4%	%0	80	8% 0.7	0.7% 34	34.5% 0.6%		%0	35.8%	
PHF	0.71	0.72	0.75	0		0.87	6.0	0.89	6.0	0		6:0	0.78	0.72	0.75	0	0	0.85 0.0	0.69 0	0.86 0.4	0.42	0	0.85	
Heavy	0	 0 	0	0	 	0		=	-		 	12	2 1	0		0		2		28 0		0	29	
Heavy %	%0	%0	%0	%0		%0			1%	%0		1.4%	2.1%	%0	%0	%0	1,1		. 0			%0	5.1%	
Lights	17	 56 	 6 	0	 	52	1 8	709	96			823	95	26	9	1 0	#	124	10 10 5	517 10	10	0	537	
Lights %	100%	100%	100%	%0		100%	100%	98.5%	%66	%0		%9.86	%6'.26	100% 1	100%	%0	98.	98.4% 90.	90.9% 94	94.9% 100	100%	%0	94.9%	
Single-Unit Trucks	0	0	0	0		0	0	D.	0	0		10	-	0	0	0		-	-	21 0	0	0	22	
Single-Unit Trucks %	%0	%0	%0	%0		%0	%0	0.7%	%0	%0		%9.0	1.1%	%0	%0	%0	0.4	0.8%	9.1% 3.	3.9% 0%	0 %0	%0	3.9%	
Buses	0	0	0	0		0	0	2	-	0		6	-	0	0	0		-	0	0 9	0	0	9	
Buses %	%0	%0	%0	%0		%0	%0	0.3%	1%	%0		0.4%	1.1%	%0	%0	%0	0.1	0.8%	1.	1.1% 0%) %0	%0	1.1%	
Articulated Trucks	0	0	0	0		0	0	4	0	0		4	0	0	0	0	7	0	0	1 0	0	0	-	
Articulated Trucks %	%0	%0	%0	%0		%0	%0	%9.0	%0	%0		0.5%	%0	%0	%0	%0	0	0 %0	0, %0	0.2% 0%) %0	%0	0.2%	
Pedestrians					4		,			,	9	,					4					6 .	,	
Pedestrians%	,			,	16.7%			,	,	,	25%			,	,		16.7%				,	- 37.5%	-0	
Bicycles on Crosswalk	,			,	0			,	,	,	-	,		,	,		0				,	0 -	,	
Bicycles on Crosswalk%					%0		,			,	4.2%						%0	•				- 0%		
Bicycles on Road	0	0	0	0	0		0	0	0	0	0		-	0	0	0	0			0	0	0 0	•	

%0

%0


%0

%0

Bicycles on Road%


Turning Movement Count Location Name: GUELPH ST & MILL ST Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis





Turning Movement Count Location Name: GUELPH ST & MILL ST Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis





Guelph St @ Mill St **Morning Peak Diagram Specified Period One Hour Peak** From: 7:45:00 **From:** 7:00:00 To: 9:00:00 To: 8:45:00 Municipality: Halton Hills Weather conditions: Rain/Cloudy Site #: 000000002 Intersection: Guelph St & Mill St Person(s) who counted: Les TFR File #: Count date: 5-Nov-2018 ** Signalized Intersection ** Major Road: Guelph St runs W/E North Leg Total: 134 Heavys 0 0 Heavys 1 East Leg Total: 1368 North Entering: 69 Trucks 0 1 Trucks 2 East Entering: 440 North Peds: East Peds: Cars 21 31 15 67 Cars 62 3 \mathbb{X} Peds Cross: Totals 21 32 Totals 65 Peds Cross: ⋈ 16 Mill St Totals Trucks Heavys Totals Heavys Trucks Cars Cars 23 374 406 0 0 15 338 370 23 54 1 55 Guelph St 407 24 Heavys Trucks Cars Totals Guelph St 1 23 25 20 14 710 744 Trucks Heavys Totals 0 2 2 0 Cars 735 890 16 22 928 \mathbb{X} Peds Cross: Peds Cross: \bowtie Cars 87 Cars 15 165 204 West Peds: 0 Trucks 0 Trucks 0 1 2 South Peds: 18 1 West Entering: 771 Heavys 2 Heavys 0 2 2 South Entering: 208 West Leg Total: 1177 Totals 15 South Leg Total: 297 Totals 89 168 **Comments**

Guelph St @ Mill St Mid-day Peak Diagram **Specified Period One Hour Peak** From: 11:00:00 **From:** 11:15:00 To: 14:00:00 To: 12:15:00 Municipality: Halton Hills Weather conditions: Rain/Cloudy Site #: 000000002 Intersection: Guelph St & Mill St Person(s) who counted: Les TFR File #: Count date: 5-Nov-2018 ** Signalized Intersection ** Major Road: Guelph St runs W/E North Leg Total: 80 Heavys 0 0 0 Heavys 0 East Leg Total: 1134 North Entering: 47 Trucks 1 Trucks 1 East Entering: 0 515 North Peds: East Peds: Cars 12 19 15 46 Cars 32 5 \mathbb{X} Peds Cross: Totals 13 19 15 Totals 33 Peds Cross: Mill St Totals Trucks Heavys Totals Heavys Trucks Cars Cars 17 424 447 0 0 408 16 6 430 78 2 80 Guelph St 491 8 Heavys Trucks Cars Totals Guelph St 0 0 6 6 10 11 452 473 0 5 5 Trucks Heavys Totals 0 Cars 595 463 13 619 \mathbb{X} Peds Cross: Peds Cross: \bowtie Cars 102 Cars 4 128 153 West Peds: 4 Trucks 0 Trucks 0 2 3 South Peds: 9 1 West Entering: 484 Heavys 2 1 South Entering: 157 Heavys 0 1 West Leg Total: 931 Totals 104 Totals 4 South Leg Total: 261 131 **Comments**

Guelph St @ Mill St **Afternoon Peak Diagram Specified Period One Hour Peak** From: 15:00:00 **From:** 16:45:00 To: 18:00:00 To: 17:45:00 Municipality: Halton Hills Weather conditions: Rain/Cloudy Site #: 000000002 Intersection: Guelph St & Mill St Person(s) who counted: Les TFR File #: Count date: 5-Nov-2018 ** Signalized Intersection ** Major Road: Guelph St runs W/E North Leg Total: 125 Heavys 0 0 0 Heavys 0 East Leg Total: 1666 North Entering: 64 Trucks 0 0 Trucks 0 East Entering: 0 982 North Peds: East Peds: Cars 27 28 9 64 Cars 61 4 \mathbb{X} Peds Cross: Totals 27 28 9 Totals 61 Peds Cross: \bowtie Mill St Totals Trucks Heavys Totals Heavys Trucks Cars Cars 10 12 876 898 0 0 14 832 853 11 10 114 1 115 Guelph St 960 11 Heavys Trucks Cars Totals Guelph St 0 16 16 532 547 11 0 11 Trucks Heavys Totals 0 Cars 559 667 10 684 \mathbb{X} Peds Cross: Cars 153 Peds Cross: \bowtie Cars 17 126 174 2 West Peds: 11 Trucks 0 Trucks 1 0 1 South Peds: 5 West Entering: 574 Heavys 0 1 South Entering: 177 Heavys 1 1 West Leg Total: 1472 Totals 154 Totals 18 South Leg Total: 331 128 **Comments**

Guelph St @ Mill St

Total Count Diagram

Municipality: Halton Hills

Site #: 000000002

Intersection: Guelph St & Mill St

TFR File #:

Count date: 5-Nov-2018 Weather conditions:

Rain/Cloudy

Person(s) who counted:

Les

** Signalized Intersection **

North Leg Total: 809 North Entering: 445

North Peds: 28 Peds Cross:

Heavys	1	3	1	5
Trucks	3	5	6	14
Cars	134	215	77	426
Totals	138	223	84	




Mill St



Major Road: Guelph St runs W/E

East Leg Total: 10097 East Entering: East Peds: 29 \mathbb{Z} Peds Cross:








Heavys	Trucks	Cars	Totals
2	2	108	112
128	99	3972	4199
0	1	55	56
130	102	4135	







Guelph St




fill St				
Cars	81	157	1011	12

Cars	Trucks	Heavys	Totals
5060	120	140	5320

Peds Cross:	\mathbb{X}
West Peds:	54
West Entering:	4367
West Leg Total:	8611







Peds Cross: \bowtie South Peds: 117 South Entering: 1282 South Leg Total: 2225

Comments

Turning Movement Count Location Name: MILL ST & DAYFOOT DR Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



										É	urning	Turning Movement Count (2 . MILL ST & DAYFOOT DR)	nt (2 . N	MLL ST	& DAYF	00T D	æ									
i. F				N Approach MILL ST	4 .				ш	E Approach EAST DRIVEWAY	h VAY				ø	S Approach MILL ST						W Approach DAYFOOT DR			Int. Total (15 min)	Int. Total (1 hr)
oran ime	Right N:W	Thru	N: H:	U-Turn N:N	Peds N:	Approach Total	Right E:N	Thru E:W	Left E:S	U-Tum E:E	Peds E:	Approach Total	Right S:E	Thru S:N	Left S:W	U-Turn S:S	Peds S:	Approach Total	Right W:S	Thru W:E	W:N	U-Turn W:W	Peds W:	Approach Total		
07:00:00	0	4	0	0	0	4	0	0	0	0	0	0	0	2	0	0	0	2	0	0	4	0	-	4	10	
07:15:00	0	2	0	0	0	2	0	0	0	0	0	0	0	2	-	0	-	9	ю	0	0	0	-	8	Ξ	
07:30:00	0	80	0	0	0	80	0	0	0	0	-	0	0	D.	0	0	0	co.	0	0	2	0	8	2	15	
07:45:00	-	10	0	0	-	1	0	0	0	0	-	0	0	41	-	0	0	15	0	0	2	0	-	2	28	64
08:00:00	0	80	0	0	0	80	0	0	-	0	2	-	0	ro.	2	0	0	7	4	0	0	0	-	4	20	74
08:15:00	-	13	-	0	0	15	0	0	0	0	-	0	0	80	2	0	0	10	-	0	2	0	2	8	28	91
08:30:00	0	6	0	0	0	6	-	0	0	0	-	-	0	2	2	0	-	4	2	0	0	0	4	2	16	92
08:45:00	2	17	0	0	0	19	0	0	0	0	0	0	0	6	-	0	0	10	2	0	4	0	0	9	35	66
BREAK	****																									
16:00:00	7	=	0	0	0	18	0	0	0	0	-	0	-	б	2	-	0	13	2	0	2	0	e	4	35	
16:15:00	2	13	-	0	0	16	0	0	0	0	0	0	0	13	0	0	0	13	2	0	0	0	0	2	31	
16:30:00	S.	6	0	0	0	14	0	0	0	0	0	0	0	2	2	0	-	7	ဇ	0	4	0	-	7	28	
16:45:00	2	14	0	0	0	19	0	0	0	0	0	0	0	7	4	0	0	E	2	0	-	0	m	ε	33	127
17:00:00	8	4	-	0	0	8	-	0	-	0	2	2	0	15	2	0	-	17	-	0	-	0	7	2	59	121
17:15:00	2	Ξ	0	0	0	13	0	0	0	0	-	0	-	12	0	0	е	13	0	0	0	0	2	0	56	116
17:30:00	2	7	0	0	-	12	0	0	0	0	-	0	0	4	0	0	0	4	-	0	-	0	4	2	18	106
17:45:00	2	10	0	0	0	12	0	0	0	0	0	0	0	1	0	0	0	11	-	0	0	0	8	1	24	97
Grand Total	35	150	က	0	2	188	2	0	23	0	1	4	2	126	19	-	7	148	24	0	23	0	36	47	387	
Approach%	18.6%	79.8%	1.6%	%0			20%	%0	20%	%0			1.4%	85.1%	12.8%	%2.0		,	51.1%	%0	48.9%	%0				
Totals %	%6	38.8%	%8.0	%0		48.6%	0.5%	%0	0.5%	%0		1%	0.5%	32.6%	4.9%	0.3%		38.2%	6.2%	%0	2.9%	%0		12.1%		
Heavy	-	ဇ	0	0			0	0	0	0		,	0	2	-	0		,	-	0	-	0				
Heavy %	2.9%	5%	%0	%0			%0	%0	%0	%0		,	%0	1.6%	5.3%	%0		,	4.2%	%0	4.3%	%0				
Bicycles	0	-	0	0		,	0	0	0	0		,	0	0	0	0		,	2	0	0	0				
i																										

%0

%0

%0

8.3%

%0

%0

%0

%0

%0

%0 %0 %0

%0

%0

0.7%

%0

Bicycle %

Turning Movement Count Location Name: MILL ST & DAYFOOT DR Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



								Pea	k Hour	: 08:00	Peak Hour: 08:00 AM - 09:00 AM		her: S	Weather: Shower Rain (4.47 °C)	ain (4.4	() · C									
Start Time				N Approach MILL ST	ach				EA	E Approach EAST DRIVEWAY	, AY				ø	S Approach MILL ST						W Approach DAYFOOT DR	G DR		Int. Total (15 min)
	Right	Thru	Left	U-Turn	n Peds	. Approach Total	Right	Thru	Left	U-Turn	Peds /	Approach Total	Right	Thru	Left	U-Turn	Peds	Approach Total	Right	Thru	Left	U-Turn	Peds	Approach Total	
00:00:80	0	8	0	0	•	8	0	0	-	0	2	-	0	22	2	0	0	7	4	0	0	0	-	4	20
08:15:00	-	55	-	0	0	15	0	0	0	0	-	0	0	80	2	0	0	10	-	0	2	0	2	е	28
08:30:00	0	6	0	0	0	ō	-	0	0	0	-	-	0	2	2	0	-	4	2	0	0	0	4	2	16
08:45:00	64	12	0	0	0	19	0	0	0	0	0	0	0	6	-	0	0	10	2	0	4	0	0	9	35
Grand Total	8	47	-	0	0	51	-	0	-	0	4	2	0	24	7	0	-	31	6	0	9	0	7	15	66
Approach%	2.9%	92.2%	5%	%0			20%	%0	20%	%0			%0	77.4%	22.6%	%0			%09	%0	40%	%0			
Totals %	3%	47.5%	, 1%	%0		51.5%	4%	%0	1%	%0		2%	%0	24.2%	7.1%	%0		31.3%	9.1%	%0	6.1%	%0		15.2%	
불	0.38	0.69		0		0.67	0.25	0	0.25	0		0.5	0	0.67	0.88	0		0.78	0.56	0	0.38	0		0.63	
Heavy	0	 	0	0		5		0		0		0	 0	8	-	0		 		0	0	0		0	
Heavy %	%0	4.3%	%0	%0		3.9%	%0	%0	%0	%0		%0	%0	8.3%	14.3%	%0		9.7%	%0	%0	%0	%0		%0	
Lights	 6 	1.54	 - 	0	 	49	 - 		-			2	101	. 22	 9	0	 	28	 6	0	 9 	0	 	15	
Lights %	100%	95.7%	, 100%	%0		96.1%	100%	%0	100%	%0		100%	%0	91.7%	85.7%	%0		90.3%	100%	%0	100%	%0		100%	
Single-Unit Trucks	0	0	0	0		0	0	0	0	0		0	0	-	0	0		-	0	0	0	0		0	
Single-Unit Trucks %	%0	%0	%0	%0		%0	%0	%0	%0	%0		%0	%0	4.2%	%0	%0		3.2%	%0	%0	%0	%0		%0	
Buses	0	-	0	0		-	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	
% sesng	%0	2.1%	%0	%0		2%	%0	%0	%0	%0		%0	%0	%0	%0	%0		%0	%0	%0	%0	%0		%0	
Articulated Trucks	0	-	0	0		-	0	0	0	0		0	0	-	-	0		2	0	0	0	0		0	
Articulated Trucks %	%0	2.1%	%0	%0		2%	%0	%0	%0	%0		%0	%0	4.2%	14.3%	%0		6.5%	%0	%0	%0	%0		%0	
Pedestrians				٠	0			,	,		4				,		-		,			,	7	,	
Pedestrians%			•		%0		,	,	,		33.3%			,	,	,	8.3%		,				58.3%		
Bicycles on Crosswalk				٠	0			,	,		0				,		0		,			,	0	,	
Bicycles on Crosswalk%				٠	%0			,	,		%0				,		%0		,			,	%0		
Bicycles on Road	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	,	
Bicycles on Road%		•			%0				,		%0		,	,		,	%0		,				%0		

Turning Movement Count Location Name: MILL ST & DAYFOOT DR Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



Start Time			_	N Approach MILL ST	£				EAS	E Approach EAST DRIVEWAY					S Approach MILL ST	oach ST					W Approach DAYFOOT DR	e DB		Int. Total (15 min)
	Right	Thru	Left	U-Turn	Peds	Approach Total	Right T	Thru	Left U-T	U-Turn Peds	Approach Total	al Right	ght Thru	u Left	t U-Turn	n Peds	Approach Total	Right	Thru	Left	U-Turn	Peds	Approach Total	
16:00:00	7	Ξ	0	0	0	18	0	0		0	0	-	6	2	-	0	13	2	0	2	0	8	4	35
16:15:00	2	13	-	0	0	91	0	0		0 0	0	0	13	0	0	0	13	2	0	0	0	0	2	31
16:30:00	2	6	0	0	0	41	0	0	0	0 0	0	0	2	8	0	-	7	6	0	4	0	-	7	28
16:45:00	2	14	0	0	0	19	0	0	0	0 0	0	0	7	4	0	0	=	2	0	-	0	e	ε	33
Grand Total	19	47	-	0	0	67	0	0	0	0 1	0	-	34	80	-	-	44	6	0	7	0	7	16	127
Approach%	28.4%	70.1%	1.5%	%0			%0	0 %0	,0 %0	%0		2.3%	% 77.3%	18.2%	% 2.3%			56.3%	%0	43.8%	%0			
Totals %	15%	37%	%8.0	%0		52.8%	%0	0 %0	,0 %0	%0	%0	0.8%	% 26.8%	% 6.3%	% 0.8%		34.6%	7.1%	%0	5.5%	%0		12.6%	
PHF	0.68	0.84	0.25	0		0.88	0	0	0	0	0	0.25					0.85	0.75	0	0.44	0		0.57	
Heavy	i - 	0	 0 	0	 	-			0		0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	0	0	0	0	 	0	- - 	0	- - 	0		2	: : : •
Heavy %	5.3%	%0	%0	%0		1.5%	%0	.0 %0	0 %0	%0	%0	%0	%0 %	%0	%0		%0	11.1%	%0	14.3%	%0		12.5%	
Lights	18	47	-	0		99	0	0	0	0	0	-			-		44	80	0	9	0		14	
Lights %	94.7%	100%	100%	%0		98.5%	%0	0 %0	,0 %0	%0	%0	100%	100%	% 100%	% 100%		100%	88.9%	%0	85.7%	%0		87.5%	
Single-Unit Trucks	-	0	0	0		-	0	0	0	0	0	0	0	0	0		0	0	0	-	0		-	
Single-Unit Trucks %	5.3%	%0	%0	%0		1.5%	%0	0 %0	,0 %0	%0	%0	%0	%0 %	%0	%0 "		%0	%0	%0	14.3%	%0		6.3%	
Buses	0	0	0	0		0	0	0	0	0	0	0	0	0	0		0	-	0	0	0		-	
% sesng	%0	%0	%0	%0		%0	%0	0 %0	,0 %0	%0	%0	%0	%0 %	%0	%0 "		%0	11.1%	%0	%0	%0		6.3%	
Articulated Trucks	0	0	0	0		0	0	0	0	0	0	0	0	0	0		0	0	0	0	0		0	
Articulated Trucks %	%0	%0	%0	%0		%0	%0	0 %0	,0 %0	%0	%0	%0	%0 %	%0	%0 "		%0	%0	%0	%0	%0		%0	
Pedestrians				,	0			,		-	•	,	•	•	•	-	,			,	,	7		
Pedestrians%		,		,	%0		,			- 11.1%		•	•	•	•	11.1%					,	77.8%		
Bicycles on Crosswalk				,	0			,		0 -	•	,	•	•	•	0	,			,	,	0		
Bicycles on Crosswalk%				,	%0		,	,	,	%0 -		,	•	•	•	%0		,	,			%0		
Bicycles on Road	0	0	0	0	0		0	0	0	0 0		J	0	0	0	0		0	0	0	0	0		

%0

%0

%0

%0

Bicycles on Road%

Turning Movement Count Location Name: MILL ST & DAYFOOT DR Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



© Mapbox, © OpenStreetMap Bicycles on Crosswalk Pedestrians 0 Peak Hour: 08:00 AM - 09:00 AM Weather: Shower Rain (4.47 °C) © mappox Dayfoot Dr

Turning Movement Count Location Name: MILL ST & DAYFOOT DR Date: Tue, Nov 03, 2020 Deployment Lead: Theo Daglis



© Mapbox, © OpenStreetMap Bicycles on Crosswalk Pedestrians 0 Peak Hour: 04:00 PM - 05:00 PM Weather: Overcast Clouds (5.94 °C) • mappox Dayfoot Dr

APPENDIX C: Corridor Growth Analysis



Project: 16-18 Mill St
Project ID: 8070-01
Intersection Guelph St & Mill St
Peak Hour AM Peak

	North of Ir	tersection		
Date	Year	Northbound	Southbound	2-Way
05-Nov-18	2018	65	69	134
09-Nov-16	2016	49	57	106
16-Dec-14	2014	65	86	151
17-Dec-12	2012	59	88	147
13-Dec-07	2007	52	61	113
21-Dec-05	2005	69	86	155
				•


Trend Point at start	58.6	70.2	128.8
Trend Point at end	61.3	79.5	140.8
Slope	-0.2	-0.7	-0.9
Annual Growth	-0.3%	-1.0%	-0.7%


	South of Ir	ntersection		
Date	Year	Northbound	Southbound	2-Way
05-Nov-18	2018	208	89	297
09-Nov-16	2016	207	114	321
16-Dec-14	2014	242	125	367
17-Dec-12	2012	243	126	369
13-Dec-07	2007	210	121	331
21-Dec-05	2005	229	172	401


Trend Point at start	218.9	98.2	317.1
Trend Point at end	228.2	155.1	383.3
Slope	-0.7	-4.4	-5.1
Annual Growth	-0.3%	-3.5%	-1.4%


	East of In	tersection		
Date	Year	Eastbound	Westbound	2-Way
05-Nov-18	2018	890	440	1330
09-Nov-16	2016	1026	425	1451
16-Dec-14	2014	937	376	1313
17-Dec-12	2012	947	404	1351
13-Dec-07	2007	986	398	1384
21-Dec-05	2005	1033	460	1493
	•			


Trend Point at start	930.9	411.7	1342.6
Trend Point at end	1015.2	423.5	1438.7
Slope	-6.5	-0.9	-7.4
Annual Growth	-0.7%	-0.2%	-0.5%











 Project:
 16-18 Mill St


 Project ID:
 8070-01

 Intersection
 Guelph St & Mill St

 Peak Hour
 PM Peak

Date	North of Ir Year	tersection Northbound	Southbound	2-Way
05-Nov-18	2018	61	64	125
09-Nov-16	2016	68	70	138
16-Dec-14	2014	85	95	180
17-Dec-12	2012	120	105	225
13-Dec-07	2007	80	88	168
21-Dec-05	2005	113	86	199


Trend Point at start	70.2	76.0	146.1
Trend Point at end	108.5	94.8	203.2
Slope	-2.9	-1.4	-4.4
Annual Growth	-3.3%	-1.7%	-2.5%





Trend Point at start	177.3	166.6	343.9
Trend Point at end	321.8	210.9	532.7
Slope	-11.1	-3.4	-14.5
Annual Growth	-4.5%	-1.8%	-3.3%


East of In	tersection		
Year	Eastbound	Westbound	2-Way
2018	684	982	1666
2016	746	1036	1782
2014	669	952	1621
2012	716	1035	1751
2007	868	1157	2025
2005	737	1038	1775
	Year 2018 2016 2014 2012 2007	Year Eastbound 2018 684 2016 746 2014 669 2012 716 2007 868	Year Eastbound Westbound 2018 684 982 2016 746 1036 2014 669 952 2012 716 1035 2007 868 1157 2005 737 1038


Trend Point at start	687.1	982.1	1669.2
Trend Point at end	794.4	1093.2	1887.6
Slope	-8.3	-8.5	-16.8
Annual Growth	-1.1%	-0.8%	-0.9%











APPENDIX D: Synchro Outputs



	ၨ	-	•	•	1	†	-	↓	
Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT	
Lane Configurations	7	f)	7	ħβ		4		4	
Traffic Volume (vph)	25	745	55	370	15	25	15	30	
Future Volume (vph)	25	745	55	370	15	25	15	30	
Turn Type	Perm	NA	Prot	NA	custom	NA	custom	NA	
Protected Phases		2	1	6					
Permitted Phases	2				8	8	4	4	
Detector Phase	2	2	1	6	8	8	4	4	
Switch Phase									
Minimum Initial (s)	30.0	30.0	6.0	30.0	8.0	8.0	8.0	8.0	
Minimum Split (s)	37.0	37.0	10.5	37.0	29.0	29.0	29.0	29.0	
Total Split (s)	39.0	39.0	12.0	51.0	29.0	29.0	29.0	29.0	
Total Split (%)	48.8%	48.8%	15.0%	63.8%	36.3%	36.3%	36.3%	36.3%	
Yellow Time (s)	5.0	5.0	3.0	5.0	4.0	4.0	4.0	4.0	
All-Red Time (s)	2.0	2.0	1.5	2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-3.0	-3.0	-0.5	-3.0		-2.0		-2.0	
Total Lost Time (s)	4.0	4.0	4.0	4.0		4.0		4.0	
Lead/Lag	Lag	Lag	Lead						
Lead-Lag Optimize?	Yes	Yes	Yes						
Recall Mode	C-Min	C-Min	None	C-Min	None	None	None	None	
Act Effct Green (s)	50.9	50.9	8.1	58.6		13.4		13.4	
Actuated g/C Ratio	0.64	0.64	0.10	0.73		0.17		0.17	
v/c Ratio	0.05	0.71	0.35	0.17		0.55		0.28	
Control Delay	10.0	18.4	39.1	4.2		12.1		22.6	
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0	
Total Delay	10.0	18.4	39.1	4.2		12.1		22.6	
LOS	В	В	D	Α		В		С	
Approach Delay		18.1		8.6		12.1		22.6	
Approach LOS		В		Α		В		С	

Intersection Summary

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.71

Intersection Signal Delay: 14.7 Intersection LOS: B
Intersection Capacity Utilization 66.7% ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	۶	→	•	←	†	↓
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	27	815	60	418	228	71
v/c Ratio	0.05	0.71	0.35	0.17	0.55	0.28
Control Delay	10.0	18.4	39.1	4.2	12.1	22.6
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	10.0	18.4	39.1	4.2	12.1	22.6
Queue Length 50th (m)	1.5	81.4	9.0	6.5	6.3	7.2
Queue Length 95th (m)	7.2	#210.1	20.8	21.7	20.9	15.1
Internal Link Dist (m)		244.8		229.4	50.3	70.6
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	543	1151	182	2419	621	456
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.05	0.71	0.33	0.17	0.37	0.16
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	•	←	•	•	†	<i>></i>	/	+	✓
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	ĵ»		ň	∱ ⊅			44			4	
Traffic Volume (vph)	25	745	5	55	370	15	15	25	170	15	30	20
Future Volume (vph)	25	745	5	55	370	15	15	25	170	15	30	20
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	4.0	4.0		4.0	4.0			4.0			4.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			1.00	
Flpb, ped/bikes	0.99	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	0.99			0.89			0.96	
Flt Protected	0.95	1.00		0.95	1.00			1.00			0.99	
Satd. Flow (prot)	1600	1808		1711	3299			1618			1743	
Flt Permitted	0.51	1.00		0.95	1.00			0.98			0.80	
Satd. Flow (perm)	854	1808		1711	3299			1583			1414	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	27	810	5	60	402	16	16	27	185	16	33	22
RTOR Reduction (vph)	0	0	0	0	2	0	0	154	0	0	18	0
Lane Group Flow (vph)	27	815	0	60	416	0	0	74	0	0	53	0
Confl. Peds. (#/hr)	8		18	18		8			3	3		3
Heavy Vehicles (%)	8%	5%	0%	2%	9%	0%	0%	4%	2%	6%	3%	0%
Turn Type	Perm	NA		Prot	NA		custom	NA		custom	NA	-
Protected Phases		2		1	6							
Permitted Phases	2	_					8	8		4	4	
Actuated Green, G (s)	46.1	46.1		5.0	55.6			11.4			11.4	
Effective Green, g (s)	49.1	49.1		5.5	58.6			13.4			13.4	
Actuated g/C Ratio	0.61	0.61		0.07	0.73			0.17			0.17	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	524	1109		117	2416			265			236	
v/s Ratio Prot	JZ 7	c0.45		c0.04	0.13			200			230	
v/s Ratio Perm	0.03	60.40		60.04	0.13			c0.05			0.04	
v/c Ratio	0.05	0.73		0.51	0.17			0.28			0.22	
Uniform Delay, d1	6.2	10.9		36.0	3.3			29.1			28.8	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.2	4.3		3.8	0.2			0.2			0.2	
Delay (s)	6.3	15.2		39.7	3.4			29.3			29.0	
Level of Service	Α	В		D	A			C			C	
Approach Delay (s)	,,	14.9		U	8.0			29.3			29.0	
Approach LOS		В			Α			C C			C C	
Intersection Summary												
HCM 2000 Control Delay			15.5	H	CM 2000	Level of	Service		В			
HCM 2000 Volume to Capac	ity ratio		0.65	.,	2111 2000	_0.0101	2011100					
Actuated Cycle Length (s)	ratio		80.08	Sı	um of lost	time (s)			14.0			
Intersection Capacity Utilizat	ion		66.7%		CU Level	. ,	ے ۔		C			
Analysis Period (min)			15		J LOVOI (or our vice						
c Critical Lane Group			10									

	٦	•	4	†	ţ	1
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	¥			4	ĵ.	
Traffic Volume (veh/h)	5	10	5	60	55	5
Future Volume (Veh/h)	5	10	5	60	55	5
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	5	11	5	65	60	5
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				208		
pX, platoon unblocked						
vC, conflicting volume	144	70	72			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	144	70	72			
tC, single (s)	6.4	6.2	4.2			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.3			
p0 queue free %	99	99	100			
cM capacity (veh/h)	845	993	1447			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	16	70	65			
Volume Left	5	5	0			
Volume Right	11	0	5			
cSH	942	1447	1700			
Volume to Capacity	0.02	0.00	0.04			
Queue Length 95th (m)	0.4	0.1	0.0			
Control Delay (s)	8.9	0.6	0.0			
Lane LOS	Α	Α	0.0			
Approach Delay (s)	8.9	0.6	0.0			
Approach LOS	A	0.0	0.0			
Intersection Summary						
Average Delay			1.2			
Intersection Capacity Utiliz	zation		17.3%	10	CU Level o	of Sarvica
Analysis Period (min)	Zauvii		17.376	IC	JO LEVEI C	n Jei vice
Analysis Penou (min)			15			

	•	-	•	•	1	†	-	ţ	
Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT	
Lane Configurations	7	ĵ.	7	∱ }		4		4	
Traffic Volume (vph)	15	545	115	855	20	30	10	30	
Future Volume (vph)	15	545	115	855	20	30	10	30	
Turn Type	Perm	NA	Prot	NA	custom	NA	custom	NA	
Protected Phases		2	1	6					
Permitted Phases	2				8	8	4	4	
Detector Phase	2	2	1	6	8	8	4	4	
Switch Phase									
Minimum Initial (s)	30.0	30.0	6.0	30.0	8.0	8.0	8.0	8.0	
Minimum Split (s)	37.0	37.0	10.5	37.0	29.0	29.0	29.0	29.0	
Total Split (s)	39.0	39.0	12.0	51.0	29.0	29.0	29.0	29.0	
Total Split (%)	48.8%	48.8%	15.0%	63.8%	36.3%	36.3%	36.3%	36.3%	
Yellow Time (s)	5.0	5.0	3.0	5.0	4.0	4.0	4.0	4.0	
All-Red Time (s)	2.0	2.0	1.5	2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-3.0	-3.0	-0.5	0.0		-2.0		-2.0	
Total Lost Time (s)	4.0	4.0	4.0	7.0		4.0		4.0	
Lead/Lag	Lag	Lag	Lead						
Lead-Lag Optimize?	Yes	Yes	Yes						
Recall Mode	C-Min	C-Min	None	C-Min	None	None	None	None	
Act Effct Green (s)	44.1	44.1	10.4	55.6		13.4		13.4	
Actuated g/C Ratio	0.55	0.55	0.13	0.70		0.17		0.17	
v/c Ratio	0.05	0.59	0.56	0.39		0.51		0.24	
Control Delay	11.7	16.6	44.2	6.5		13.9		19.9	
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0	
Total Delay	11.7	16.6	44.2	6.5		13.9		19.9	
LOS	В	В	D	А		В		В	
Approach Delay		16.5		10.9		13.9		19.9	
Approach LOS		В		В		В		В	

Intersection Summary

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.59

Intersection Signal Delay: 13.3 Intersection LOS: B
Intersection Capacity Utilization 76.7% ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	۶	→	•	←	†	ļ
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	16	603	125	945	196	71
v/c Ratio	0.05	0.59	0.56	0.39	0.51	0.24
Control Delay	11.7	16.6	44.2	6.5	13.9	19.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	11.7	16.6	44.2	6.5	13.9	19.9
Queue Length 50th (m)	1.0	56.0	18.5	22.5	8.1	6.4
Queue Length 95th (m)	5.2	119.1	#46.2	60.1	21.3	14.3
Internal Link Dist (m)		244.8		229.4	50.3	70.6
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	306	1015	225	2451	592	529
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.05	0.59	0.56	0.39	0.33	0.13
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	•	←	•	4	†	~	/	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	f.		*	↑ Ъ			4			4	
Traffic Volume (vph)	15	545	10	115	855	15	20	30	130	10	30	25
Future Volume (vph)	15	545	10	115	855	15	20	30	130	10	30	25
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	4.0	4.0		4.0	7.0			4.0			4.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			0.99	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	1.00			0.90			0.95	
Flt Protected	0.95	1.00		0.95	1.00			0.99			0.99	
Satd. Flow (prot)	1741	1840		1728	3530			1647			1772	
Flt Permitted	0.30	1.00		0.95	1.00			0.96			0.92	
Satd. Flow (perm)	555	1840		1728	3530			1588			1636	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	16	592	11	125	929	16	22	33	141	11	33	27
RTOR Reduction (vph)	0	0	0	0	1	0	0	117	0	0	22	0
Lane Group Flow (vph)	16	603	0	125	944	0	0	79	0	0	49	0
Confl. Peds. (#/hr)	4	000	5	5	, , , ,	4	11	, ,	4	4	17	11
Heavy Vehicles (%)	0%	3%	0%	1%	2%	0%	0%	0%	2%	0%	0%	0%
Turn Type	Perm	NA	070	Prot	NA	070	custom	NA	270	custom	NA	070
Protected Phases	T CITII	2		1	6		Custom	INA		Custom	INA	
Permitted Phases	2	2			U		8	8		4	4	
Actuated Green, G (s)	41.2	41.2		9.9	55.6		0	11.4			11.4	
Effective Green, g (s)	44.2	44.2		10.4	55.6			13.4			13.4	
Actuated g/C Ratio	0.55	0.55		0.13	0.70			0.17			0.17	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	306	1016		224	2453			265			274	
v/s Ratio Prot	300	c0.33		c0.07	0.27			203			2/4	
v/s Ratio Prot v/s Ratio Perm	0.03	60.55		CU.U7	0.27			c0.05			0.03	
v/c Ratio	0.05	0.59		0.56	0.38			0.30			0.03	
Uniform Delay, d1	8.2	11.9		32.6	5.1			29.2			28.6	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.3	2.5		3.0	0.5			0.2			0.1	
Delay (s)	8.6	14.5		35.6	5.5			29.4			28.7	
Level of Service	0.0 A	14.5 B		33.0 D	3.5 A			27.4 C			20.7 C	
Approach Delay (s)	Α	14.3		U	9.1			29.4			28.7	
Approach LOS		14.3 B			7. I			27.4 C			20.7 C	
Intersection Summary								0			0	
HCM 2000 Control Delay			13.5	<u></u>	CM 2000	L aval of	Sarvico		В			
HCM 2000 Control Delay HCM 2000 Volume to Capac	rity ratio		0.54	П	CIVI 2000	Level OI	JEI VILE		В			
Actuated Cycle Length (s)	nty ratio		80.0	Çı	um of lost	time (c)			14.0			
Intersection Capacity Utilizat	ion		76.7%		U Level		<u> </u>		14.0 D			
Analysis Period (min)	IUII		15	IC	O Level (JI JEI VICE	-		U			
c Critical Lane Group			10									

	•	•	1	†		4
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			4	1>	
Traffic Volume (veh/h)	10	10	10	50	55	20
Future Volume (Veh/h)	10	10	10	50	55	20
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.91
Hourly flow rate (vph)	11	11	11	54	60	22
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				208		
pX, platoon unblocked						
vC, conflicting volume	154	78	89			
vC1, stage 1 conf vol	101	, 0	<u> </u>			
vC2, stage 2 conf vol						
vCu, unblocked vol	154	78	89			
tC, single (s)	6.5	6.3	4.1			
tC, 2 stage (s)	0.0	0.0				
tF (s)	3.6	3.4	2.2			
p0 queue free %	99	99	99			
cM capacity (veh/h)	800	953	1510			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	22	65	82			
Volume Left	11	11	0			
Volume Right	11	0	22			
cSH	869	1510	1700			
Volume to Capacity	0.03	0.01	0.05			
Queue Length 95th (m)	0.6	0.2	0.0			
Control Delay (s)	9.2	1.3	0.0			
Lane LOS	А	Α				
Approach Delay (s)	9.2	1.3	0.0			
Approach LOS	А					
Intersection Summary						
Average Delay			1.7			
Intersection Capacity Utiliz	ation		19.9%	IC	CU Level o	f Service
Analysis Period (min)			15			
J 212 1 2112 21 (11111)						

	•	→	•	•	4	†	>	ļ	
Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT	
Lane Configurations	7	^	7	∱ }		4		4	
Traffic Volume (vph)	30	745	55	370	15	30	60	40	
Future Volume (vph)	30	745	55	370	15	30	60	40	
Turn Type	Perm	NA	Prot	NA	custom	NA	custom	NA	
Protected Phases		2	1	6					
Permitted Phases	2				8	8	4	4	
Detector Phase	2	2	1	6	8	8	4	4	
Switch Phase									
Minimum Initial (s)	30.0	30.0	6.0	30.0	8.0	8.0	8.0	8.0	
Minimum Split (s)	37.0	37.0	10.5	37.0	29.0	29.0	29.0	29.0	
Total Split (s)	39.0	39.0	12.0	51.0	29.0	29.0	29.0	29.0	
Total Split (%)	48.8%	48.8%	15.0%	63.8%	36.3%	36.3%	36.3%	36.3%	
Yellow Time (s)	5.0	5.0	3.0	5.0	4.0	4.0	4.0	4.0	
All-Red Time (s)	2.0	2.0	1.5	2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-3.0	-3.0	-0.5	-3.0		-2.0		-2.0	
Total Lost Time (s)	4.0	4.0	4.0	4.0		4.0		4.0	
Lead/Lag	Lag	Lag	Lead						
Lead-Lag Optimize?	Yes	Yes	Yes						
Recall Mode	C-Min	C-Min	None	C-Min	None	None	None	None	
Act Effct Green (s)	49.2	49.2	8.1	56.9		15.1		15.1	
Actuated g/C Ratio	0.62	0.62	0.10	0.71		0.19		0.19	
v/c Ratio	0.06	0.73	0.35	0.19		0.52		0.71	
Control Delay	10.9	20.4	39.1	4.6		11.3		46.0	
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0	
Total Delay	10.9	20.4	39.1	4.6		11.3		46.0	
LOS	В	С	D	Α		В		D	
Approach Delay		20.0		8.8		11.3		46.0	
Approach LOS		С		А		В		D	
Intersection Summary									
Cycle Length: 80									

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.73

Intersection Signal Delay: 17.6 Intersection LOS: B Intersection Capacity Utilization 76.4% ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	٠	→	•	←	†	↓
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	33	815	60	440	234	135
v/c Ratio	0.06	0.73	0.35	0.19	0.52	0.71
Control Delay	10.9	20.4	39.1	4.6	11.3	46.0
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	10.9	20.4	39.1	4.6	11.3	46.0
Queue Length 50th (m)	2.1	92.6	9.0	8.6	6.8	18.5
Queue Length 95th (m)	8.3	#210.1	20.8	22.4	22.0	31.9
Internal Link Dist (m)		244.8		229.4	42.0	68.3
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	515	1112	182	2341	623	304
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.06	0.73	0.33	0.19	0.38	0.44
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	•	←	•	4	†	/	>	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	f.		ሻ	↑ Ъ			4			4	
Traffic Volume (vph)	30	745	5	55	370	35	15	30	170	60	40	25
Future Volume (vph)	30	745	5	55	370	35	15	30	170	60	40	25
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	4.0	4.0		4.0	4.0			4.0			4.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			1.00	
Flpb, ped/bikes	0.99	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	0.99			0.89			0.97	
Flt Protected	0.95	1.00		0.95	1.00			1.00			0.98	
Satd. Flow (prot)	1600	1808		1711	3282			1623			1736	
Flt Permitted	0.50	1.00		0.95	1.00			0.98			0.53	
Satd. Flow (perm)	837	1808		1711	3282			1590			940	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	33	810	5	60	402	38	16	33	185	65	43	27
RTOR Reduction (vph)	0	0	0	0	6	0	0	150	0	0	13	0
Lane Group Flow (vph)	33	815	0	60	434	0	0	84	0	0	122	0
Confl. Peds. (#/hr)	8	010	18	18	101	8		01	3	3	122	· ·
Heavy Vehicles (%)	8%	5%	0%	2%	9%	0%	0%	4%	2%	6%	3%	0%
Turn Type	Perm	NA	070	Prot	NA	070	custom	NA	270	custom	NA	070
Protected Phases	I CIIII	2		1	6		Custom	INA		Custom	INA	
Permitted Phases	2	2		•	U		8	8		4	4	
Actuated Green, G (s)	44.4	44.4		5.0	53.9		U	13.1		7	13.1	
Effective Green, g (s)	47.4	47.4		5.5	56.9			15.1			15.1	
Actuated g/C Ratio	0.59	0.59		0.07	0.71			0.19			0.19	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	495	1071		117	2334			300			177	
v/s Ratio Prot	470	c0.45		c0.04	0.13			300			177	
v/s Ratio Perm	0.04	CU.45		CU.U4	0.13			0.05			c0.13	
v/c Ratio	0.04	0.76		0.51	0.19			0.03			0.69	
Uniform Delay, d1	6.9	12.1		36.0	3.8			27.8			30.3	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.3	5.1		3.8	0.2			0.2			8.6	
Delay (s)	7.2	17.2		39.7	4.0			28.0			38.9	
Level of Service	7.2 A	17.2 B		37.7 D	4.0 A			20.0 C			30.9 D	
Approach Delay (s)		16.8		U	8.3			28.0			38.9	
Approach LOS		10.8 B			0.5 A			20.0 C			30.9 D	
Intersection Summary					, , , , , , , , , , , , , , , , , , ,							
HCM 2000 Control Delay			17.6	<u> </u>	CM 2000	L aval of	Sarvica		В			
HCM 2000 Collino Delay HCM 2000 Volume to Capaci	ty ratio		0.75	П	CIVI 2000	Level OI	JEI VILE		В			
Actuated Cycle Length (s)	ty ratio		80.0	Cı	um of lost	time (c)			14.0			
Intersection Capacity Utilization	on		76.4%		U Level (<u> </u>		14.0 D			
Analysis Period (min)	UIT		15	10	O Level (JI JEI VICE	-		U			
c Critical Lane Group			10									

	٦	•	4	†		1
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	¥			र्स	î,	
Traffic Volume (veh/h)	10	45	20	70	60	10
Future Volume (Veh/h)	10	45	20	70	60	10
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	11	49	22	76	65	11
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				205		
pX, platoon unblocked						
vC, conflicting volume	198	78	83			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	198	78	83			
tC, single (s)	6.4	6.2	4.2			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.3			
p0 queue free %	99	95	98			
cM capacity (veh/h)	779	983	1433			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	60	98	76			
Volume Left	11	22	0			
Volume Right	49	0	11			
cSH	938	1433	1700			
Volume to Capacity	0.06	0.02	0.04			
Queue Length 95th (m)	1.6	0.02	0.0			
Control Delay (s)	9.1	1.8	0.0			
Lane LOS	7.1 A	Α	0.0			
Approach Delay (s)	9.1	1.8	0.0			
Approach LOS	9.1 A	1.0	0.0			
	A					
Intersection Summary						
Average Delay			3.1			
Intersection Capacity Utili	zation		21.5%	IC	CU Level c	f Service
Analysis Period (min)			15			

Lane Group EBL EBT WBL WBT NBL NBT SBL SBT Lane Configurations 1 1 1 1 4
Traffic Volume (vph) 20 545 115 855 20 40 40 40 Future Volume (vph) 20 545 115 855 20 40 40 40 Turn Type Perm NA Prot NA custom NA custom NA
Future Volume (vph) 20 545 115 855 20 40 40 40 Turn Type Perm NA Prot NA custom NA custom NA
Turn Type Perm NA Prot NA custom NA custom NA
71
Dretested Dhases
Protected Phases 2 1 6
Permitted Phases 2 8 8 4 4
Detector Phase 2 2 1 6 8 8 4 4
Switch Phase
Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 8.0
Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0
Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 29.0
Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% 36.3%
Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 4.0
All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 2.0
Lost Time Adjust (s) -1.0 -1.0 -1.0 -1.0 -1.0 -1.0
Total Lost Time (s) 6.0 6.0 3.5 6.0 5.0 5.0
Lead/Lag Lag Lead
Lead-Lag Optimize? Yes Yes Yes
Recall Mode C-Min C-Min None C-Min Min Min Min Min
Act Effct Green (s) 41.8 41.8 10.8 56.1 12.9 12.9
Actuated g/C Ratio 0.52 0.52 0.14 0.70 0.16 0.16
v/c Ratio 0.08 0.63 0.54 0.40 0.55 0.57
Control Delay 13.4 19.2 42.6 6.4 16.0 33.9
Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0
Total Delay 13.4 19.2 42.6 6.4 16.0 33.9
LOS B B D A B C
Approach Delay 19.0 10.4 16.0 33.9
Approach LOS B B C

Intersection Summary

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.63

Intersection Signal Delay: 14.9 Intersection LOS: B
Intersection Capacity Utilization 81.3% ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	۶	→	•	←	†	↓
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	22	603	125	994	206	119
v/c Ratio	0.08	0.63	0.54	0.40	0.55	0.57
Control Delay	13.4	19.2	42.6	6.4	16.0	33.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	13.4	19.2	42.6	6.4	16.0	33.9
Queue Length 50th (m)	1.6	62.2	18.4	24.3	9.9	14.5
Queue Length 95th (m)	7.0	#137.9	#44.4	61.7	24.1	25.6
Internal Link Dist (m)		244.8		229.4	42.0	68.3
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	275	961	234	2459	578	366
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.08	0.63	0.53	0.40	0.36	0.33
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	•	←	•	•	†	~	/	↓	4
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	f.		ሻ	∱ ∱			4			4	
Traffic Volume (vph)	20	545	10	115	855	60	20	40	130	40	40	30
Future Volume (vph)	20	545	10	115	855	60	20	40	130	40	40	30
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	6.0	6.0		3.5	6.0			5.0			5.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			0.99	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	0.99			0.91			0.96	
Flt Protected	0.95	1.00		0.95	1.00			0.99			0.98	
Satd. Flow (prot)	1741	1840		1728	3502			1659			1782	
Flt Permitted	0.29	1.00		0.95	1.00			0.96			0.64	
Satd. Flow (perm)	528	1840		1728	3502			1603			1162	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	22	592	11	125	929	65	22	43	141	43	43	33
RTOR Reduction (vph)	0	0	0	0	4	0	0	117	0	0	21	0
Lane Group Flow (vph)	22	603	0	125	990	0	0	89	0	0	98	0
Confl. Peds. (#/hr)	4		5	5		4	11		4	4		11
Heavy Vehicles (%)	0%	3%	0%	1%	2%	0%	0%	0%	2%	0%	0%	0%
Turn Type	Perm	NA		Prot	NA		custom	NA		custom	NA	
Protected Phases	1 01111	2		1	6		oustonn			odotom	1471	
Permitted Phases	2	_		•			8	8		4	4	
Actuated Green, G (s)	40.8	40.8		9.8	55.1			11.9		•	11.9	
Effective Green, g (s)	41.8	41.8		10.8	56.1			12.9			12.9	
Actuated g/C Ratio	0.52	0.52		0.14	0.70			0.16			0.16	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	275	961		233	2455			258			187	
v/s Ratio Prot	213	c0.33		c0.07	0.28			230			107	
v/s Ratio Perm	0.04	60.55		60.07	0.20			0.06			c0.08	
v/c Ratio	0.04	0.63		0.54	0.40			0.35			0.52	
Uniform Delay, d1	9.5	13.6		32.3	5.0			29.8			30.7	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.6	3.1		2.4	0.5			0.3			1.2	
Delay (s)	10.1	16.7		34.6	5.5			30.1			32.0	
Level of Service	В	В		C	Α			C			C	
Approach Delay (s)	U	16.4		O O	8.7			30.1			32.0	
Approach LOS		В			Α			C			C	
Intersection Summary												
HCM 2000 Control Delay			14.5	H	CM 2000	Level of	Service		В			
HCM 2000 Volume to Capac	city ratio		0.60	''			_ 0100					
Actuated Cycle Length (s)			80.0	Si	um of lost	t time (s)			15.5			
Intersection Capacity Utiliza	tion		81.3%		CU Level		e		D			
Analysis Period (min)			15	10	J 25701 (. O 51 V160						
c Critical Lane Group												

	٦	•	4	†		1
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	¥			4	f)	
Traffic Volume (veh/h)	15	35	40	55	60	30
Future Volume (Veh/h)	15	35	40	55	60	30
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	16	38	43	60	65	33
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)				,,,,		
Upstream signal (m)				205		
pX, platoon unblocked						
vC, conflicting volume	234	88	105			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	234	88	105			
tC, single (s)	6.5	6.3	4.1			
tC, 2 stage (s)						
tF (s)	3.6	3.4	2.2			
p0 queue free %	98	96	97			
cM capacity (veh/h)	703	940	1490			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	<u>EB 1</u> 54	103	98			
Volume Left	16	43	98			
	38	43	33			
Volume Right cSH	854		1700			
Volume to Capacity	0.06	1490	0.06			
Queue Length 95th (m)	1.6	0.03				
			0.0			
Control Delay (s)	9.5	3.3	0.0			
Lane LOS	A	A	0.0			
Approach LOS	9.5	3.3	0.0			
Approach LOS	А					
Intersection Summary						
Average Delay			3.3			
Intersection Capacity Utiliz	zation		21.8%	IC	CU Level o	f Service
Analysis Period (min)			15			

	•	→	•	•	1	†	-	↓	
Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT	
Lane Configurations	7	f)	7	ħβ		4		4	
Traffic Volume (vph)	30	745	55	370	15	30	70	45	
Future Volume (vph)	30	745	55	370	15	30	70	45	
Turn Type	Perm	NA	Prot	NA	custom	NA	custom	NA	
Protected Phases		2	1	6					
Permitted Phases	2				8	8	4	4	
Detector Phase	2	2	1	6	8	8	4	4	
Switch Phase									
Minimum Initial (s)	30.0	30.0	6.0	30.0	8.0	8.0	8.0	8.0	
Minimum Split (s)	37.0	37.0	10.5	37.0	29.0	29.0	29.0	29.0	
Total Split (s)	39.0	39.0	12.0	51.0	29.0	29.0	29.0	29.0	
Total Split (%)	48.8%	48.8%	15.0%	63.8%	36.3%	36.3%	36.3%	36.3%	
Yellow Time (s)	5.0	5.0	3.0	5.0	4.0	4.0	4.0	4.0	
All-Red Time (s)	2.0	2.0	1.5	2.0	2.0	2.0	2.0	2.0	
Lost Time Adjust (s)	-3.0	-3.0	-0.5	-3.0		-2.0		-2.0	
Total Lost Time (s)	4.0	4.0	4.0	4.0		4.0		4.0	
Lead/Lag	Lag	Lag	Lead						
Lead-Lag Optimize?	Yes	Yes	Yes						
Recall Mode	C-Min	C-Min	None	C-Min	None	None	None	None	
Act Effct Green (s)	48.3	48.3	8.1	56.0		16.0		16.0	
Actuated g/C Ratio	0.60	0.60	0.10	0.70		0.20		0.20	
v/c Ratio	0.07	0.75	0.35	0.19		0.50		0.77	
Control Delay	11.3	21.5	39.1	4.9		10.7		50.7	
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0	
Total Delay	11.3	21.5	39.1	4.9		10.7		50.7	
LOS	В	С	D	Α		В		D	
Approach Delay		21.1		9.0		10.7		50.7	
Approach LOS		С		А		В		D	

Intersection Summary

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.77

Intersection Signal Delay: 18.8 Intersection LOS: B
Intersection Capacity Utilization 78.3% ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	۶	→	•	•	†	↓
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	33	815	60	445	234	152
v/c Ratio	0.07	0.75	0.35	0.19	0.50	0.77
Control Delay	11.3	21.5	39.1	4.9	10.7	50.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	11.3	21.5	39.1	4.9	10.7	50.7
Queue Length 50th (m)	2.3	97.7	9.0	9.5	6.6	21.4
Queue Length 95th (m)	8.3	#210.1	20.8	22.4	22.0	36.6
Internal Link Dist (m)		244.8		229.4	42.0	68.3
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	502	1092	182	2305	623	303
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.07	0.75	0.33	0.19	0.38	0.50
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	€	←	•	•	†	<i>></i>	/	+	✓
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	7	1>		*	ħβ			4			4	
Traffic Volume (vph)	30	745	5	55	370	40	15	30	170	70	45	25
Future Volume (vph)	30	745	5	55	370	40	15	30	170	70	45	25
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	4.0	4.0		4.0	4.0			4.0			4.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			1.00	
Flpb, ped/bikes	0.99	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	0.99			0.89			0.98	
Flt Protected	0.95	1.00		0.95	1.00			1.00			0.98	
Satd. Flow (prot)	1600	1808		1711	3278			1623			1733	
Flt Permitted	0.49	1.00		0.95	1.00			0.98			0.53	
Satd. Flow (perm)	833	1808		1711	3278			1590			940	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	33	810	5	60	402	43	16	33	185	76	49	27
RTOR Reduction (vph)	0	0	0	0	8	0	0	148	0	0	11	0
Lane Group Flow (vph)	33	815	0	60	438	0	0	86	0	0	141	0
Confl. Peds. (#/hr)	8		18	18		8			3	3		3
Heavy Vehicles (%)	8%	5%	0%	2%	9%	0%	0%	4%	2%	6%	3%	0%
Turn Type	Perm	NA		Prot	NA		custom	NA		custom	NA	-
Protected Phases		2		1	6							
Permitted Phases	2	_		•	_		8	8		4	4	
Actuated Green, G (s)	43.5	43.5		5.0	53.0			14.0			14.0	
Effective Green, g (s)	46.5	46.5		5.5	56.0			16.0			16.0	
Actuated g/C Ratio	0.58	0.58		0.07	0.70			0.20			0.20	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	484	1050		117	2294			318			188	
v/s Ratio Prot	707	c0.45		c0.04	0.13			310			100	
v/s Ratio Perm	0.04	60.40		CO.O-1	0.13			0.05			c0.15	
v/c Ratio	0.07	0.78		0.51	0.19			0.27			0.75	
Uniform Delay, d1	7.3	12.8		36.0	4.2			27.1			30.1	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.3	5.6		3.8	0.2			0.2			13.3	
Delay (s)	7.6	18.4		39.7	4.3			27.2			43.4	
Level of Service	7.0 A	В		D	Α.5			C			D	
Approach Delay (s)	,,	18.0			8.5			27.2			43.4	
Approach LOS		В			Α			C			D	
Intersection Summary												
HCM 2000 Control Delay			18.7	Н	CM 2000	Level of	Service		В			
HCM 2000 Volume to Capac	ity ratio		0.77	11	2000		2011100					
Actuated Cycle Length (s)	ratio		80.0	Sı	um of lost	time (s)			14.0			
Intersection Capacity Utilizat	ion		78.3%		U Level o		ρ		D			
Analysis Period (min)			15	10	J LOVOI (or our vice						
c Critical Lane Group												

	۶	•	•	†	ļ	✓
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	¥			4	f)	
Traffic Volume (veh/h)	10	45	20	75	75	10
Future Volume (Veh/h)	10	45	20	75	75	10
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	11	49	22	82	82	11
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				205		
pX, platoon unblocked						
vC, conflicting volume	220	94	100			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	220	94	100			
tC, single (s)	6.4	6.2	4.2			
tC, 2 stage (s)						
tF (s)	3.5	3.3	2.3			
p0 queue free %	99	95	98			
cM capacity (veh/h)	756	962	1412			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	60	104	93			
Volume Left	11	22	0			
Volume Right	49	0	11			
cSH	916	1412	1700			
Volume to Capacity	0.07	0.02	0.05			
Queue Length 95th (m)	1.7	0.4	0.0			
Control Delay (s)	9.2	1.7	0.0			
Lane LOS	A	Α				
Approach Delay (s)	9.2	1.7	0.0			
Approach LOS	A		0.0			
Intersection Summary						
Average Delay			2.8			
Intersection Capacity Utilization	ation		21.7%	IC	CU Level c	f Service
Analysis Period (min)			15		, _5.0.0	
			- 10			

BBL BBR NBL NBT SBR SBR
Traffic Volume (veh/h) 0 15 5 80 70 0 Future Volume (Veh/h) 0 15 5 80 70 0 Sign Control Stop Free Free Grade 0% 0% 0% 0% Peak Hour Factor 0.92 0.92 0.92 0.92 0.92 0.92 Hourly flow rate (vph) 0 16 5 87 76 0 Pedestrians Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median storage veh) Upstream signal (m) pX, platoon unblocked vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB1 NB1 SB1 Volume Total 16 92 76 Volume Right 16 0 0 CSH 50 0 152 1700
Traffic Volume (veh/h) 0 15 5 80 70 0 Future Volume (Veh/h) 0 15 5 80 70 0 Sign Control Stop Free Free Grade 0% 0% 0% 0% Peak Hour Factor 0.92 0.92 0.92 0.92 0.92 0.92 Hourly flow rate (vph) 0 16 5 87 76 0 Pedestrians Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median storage veh) Upstream signal (m) 248 pX, platoon unblocked vC, conflicting volume vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Right 16 0 0 CSH 170 0 98 100 cSH 1523 1700
Future Volume (Veh/h) 0 15 5 80 70 0 Sign Control Stop Free Free Grade 0% 0% 0% Peak Hour Factor 0.92 0.92 0.92 0.92 0.92 0.92 Hourly flow rate (vph) 0 16 5 87 76 0 Pedestrians Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median type None None Median storage veh) Upstream signal (m) 248 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB1 NB1 SB1 Volume Total 16 92 76 Volume Right 16 0 0 cSH 162 0.92 0.92 0.92 0.92 0.92 None None None None A 6 76 76 76 76 76 76 76 76 76 76 76 76 7
Grade 0% 0% 0% Peak Hour Factor 0.92
Peak Hour Factor 0.92
Hourly flow rate (vph) 0 16 5 87 76 0 Pedestrians Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median type None None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Right 16 0 0 cSH 985 1523 1700
Pedestrians Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median type None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Lane Width (m) Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median type Median storage veh) Upstream signal (m) pX, platoon unblocked vC, conflicting volume vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol tC, single (s) tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 0 0 0 cSH 985 1523 1700
Walking Speed (m/s) Percent Blockage Right turn flare (veh) Median type None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 vC2, stage (s) 6.4 6.2 4.1 4.1 4.1 4.1 4.1 4.1 4.1 4.1 4.2 4.1 4.2 4.1 4.2 4.1 4.2
Percent Blockage Right turn flare (veh) Median type None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked VC, conflicting volume 173 76 76 vC1, stage 1 conf vol VC2, stage 2 conf vol VC4, unblocked vol 173 76 76 76 tC, single (s) 6.4 6.2 4.1 4.1 4.1 4.1 4.1 4.1 4.1 4.1 4.2
Right turn flare (veh) Median type Median storage veh) Upstream signal (m) pX, platoon unblocked vC, conflicting volume vC2, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol tC, single (s) tF (s) p0 queue free % 100 p1 yes
Median type None None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked 248 vC, conflicting volume 173 76 76 vC1, stage 1 conf vol 76 76 76 vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) 152 1523 tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Right 16 0 0 cSH 985 1523 1700
Median type None None Median storage veh) Upstream signal (m) 248 pX, platoon unblocked 248 vC, conflicting volume 173 76 76 vC1, stage 1 conf vol 76 76 76 vCu, unblocked vol 173 76 76 76 tC, single (s) 6.4 6.2 4.1 4.1 76
Median storage veh) Upstream signal (m) 248 pX, platoon unblocked 76 vC, conflicting volume 173 76 76 vC1, stage 1 conf vol 76 76 vC2, stage 2 conf vol 76 76 vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) 15 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Upstream signal (m) pX, platoon unblocked vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH P85 1523 1700
vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
vC, conflicting volume 173 76 76 vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
vC1, stage 1 conf vol vC2, stage 2 conf vol vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
vCu, unblocked vol 173 76 76 tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) 5 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
tC, single (s) 6.4 6.2 4.1 tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
tC, 2 stage (s) tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
tF (s) 3.5 3.3 2.2 p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
p0 queue free % 100 98 100 cM capacity (veh/h) 814 985 1523 Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Direction, Lane # EB 1 NB 1 SB 1 Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Volume Total 16 92 76 Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Volume Left 0 5 0 Volume Right 16 0 0 cSH 985 1523 1700
Volume Right 16 0 0 cSH 985 1523 1700
cSH 985 1523 1700
Queue Length 95th (m) 0.4 0.1 0.0
Control Delay (s) 8.7 0.4 0.0
Lane LOS A A
Approach Delay (s) 8.7 0.4 0.0
Approach LOS A
Intersection Summary
Average Delay 1.0
Intersection Capacity Utilization 18.3% ICU Level of Service
Analysis Period (min) 15

Lane Group		•	-	•	•	1	†	-	ļ	
Traffic Volume (vph) 20 545 115 855 20 40 45 45 Future Volume (vph) 20 545 115 855 20 40 45 45 Turn Type Perm NA Prot NA custom NA custom NA Permitted Phases 2 1 6 8 8 4 4 Detector Phase 2 2 1 6 8 8 4 4 Switch Phase 8 8 4 4 4 4 8 Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0	Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT	
Traffic Volume (vph) 20 545 115 855 20 40 45 45 Future Volume (vph) 20 545 115 855 20 40 45 45 Turn Type Perm NA Prot NA custom NA custom NA Permitted Phases 2 1 6 8 8 4 4 Detector Phase 2 2 1 6 8 8 4 4 Switch Phase 8 8 4 4 4 5 5 8 8 4 4 4 6 8 8 4 4 4 6 8 8 4 4 4 4 8 8 4 4 4 4 8 8 4 4 4 4 4 8 8 3 4 4 4 4 4 4 4 4 4 <	Lane Configurations	7	₽	ሻ	∱ }		4		4	
Turn Type Perm NA Prot NA custom NA custom NA Protected Phases 2 1 6 8 8 4 4 Detector Phase 2 2 1 6 8 8 4 4 Switch Phase Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0	Traffic Volume (vph)	20	545	115		20	40	45	45	
Protected Phases 2 1 6 Permitted Phases 2 2 1 6 8 8 4 4 Detector Phase 2 2 1 6 8 8 4 4 Switch Phase Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% <td>Future Volume (vph)</td> <td>20</td> <td>545</td> <td>115</td> <td>855</td> <td>20</td> <td>40</td> <td>45</td> <td>45</td> <td></td>	Future Volume (vph)	20	545	115	855	20	40	45	45	
Permitted Phases 2 2 2 1 6 8 8 4 4 Switch Phase 30.0 30.0 6.0 30.0 8.0 8.0 8.0 8.0 Minimum Initial (s) 30.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0 2.0	Turn Type	Perm	NA	Prot	NA	custom	NA	custom	NA	
Detector Phase 2 2 1 6 8 8 4 4 Switch Phase Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 Lost Time (s) 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 Lead/Lag Lag Lag Lead Lead Lead Lead Lead Lead Lead None None None None None	Protected Phases		2	1	6					
Switch Phase Minimum Initial (s) 30.0 30.0 30.0 30.0 8.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% <td>Permitted Phases</td> <td></td> <td></td> <td></td> <td></td> <td>8</td> <td>8</td> <td>4</td> <td>4</td> <td></td>	Permitted Phases					8	8	4	4	
Minimum Initial (s) 30.0 30.0 6.0 30.0 8.0 8.0 8.0 Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 2.0 2.0 Lost Time (s) 4.0 </td <td>Detector Phase</td> <td>2</td> <td>2</td> <td>1</td> <td>6</td> <td>8</td> <td>8</td> <td>4</td> <td>4</td> <td></td>	Detector Phase	2	2	1	6	8	8	4	4	
Minimum Split (s) 37.0 37.0 10.5 37.0 29.0 29.0 29.0 29.0 Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 <td>Switch Phase</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	Switch Phase									
Total Split (s) 39.0 39.0 12.0 51.0 29.0 29.0 29.0 Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 2.0 2.0 Lost Time (s) 4.0 4.0 4.0 4.0 4.0 4.0 4.0 Lead/Lag Lag Lag Lead Lead<										
Total Split (%) 48.8% 48.8% 15.0% 63.8% 36.3% 36.3% 36.3% Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 2.0 2.0 2.0 Total Lost Time (s) 4.0			37.0							
Yellow Time (s) 5.0 5.0 3.0 5.0 4.0 4.0 4.0 4.0 All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 -2.0 -2.0 Total Lost Time (s) 4.0										
All-Red Time (s) 2.0 2.0 1.5 2.0 2.0 2.0 2.0 2.0 Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 -2.0 Total Lost Time (s) 4.0 4.0 4.0 4.0 4.0 4.0 Lead/Lag Lag Lag Lead Lead Lead Lead Lead-Lag Optimize? Yes Yes Yes Yes Yes None None <td< td=""><td></td><td></td><td></td><td></td><td></td><td>36.3%</td><td></td><td>36.3%</td><td></td><td></td></td<>						36.3%		36.3%		
Lost Time Adjust (s) -3.0 -3.0 -0.5 -3.0 -2.0 -2.0 Total Lost Time (s) 4.0 4.0 4.0 4.0 4.0 4.0 Lead/Lag Lag Lag Lead Lead Lead Lead Lead-Lag Optimize? Yes Yes Yes Yes Yes Yes Recall Mode C-Min C-Min None None None None None Act Effct Green (s) 43.3 43.3 10.4 57.7 14.3 14.3 Actuated g/C Ratio 0.54 0.54 0.13 0.72 0.18 0.18 v/c Ratio 0.08 0.61 0.56 0.40 0.51 0.56 Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 Los </td <td></td>										
Total Lost Time (s) 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 4.0 Lead						2.0		2.0		
Lead/Lag Lag Lag Lead Lead-Lag Optimize? Yes Yes Yes Recall Mode C-Min C-Min None None<										
Lead-Lag Optimize? Yes		4.0		4.0	4.0		4.0		4.0	
Recall Mode C-Min C-Min None C-Min None None None None None Act Effct Green (s) 43.3 43.3 10.4 57.7 14.3 14.3 Actuated g/C Ratio 0.54 0.54 0.13 0.72 0.18 0.18 v/c Ratio 0.08 0.61 0.56 0.40 0.51 0.56 Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9										
Act Effct Green (s) 43.3 43.3 10.4 57.7 14.3 14.3 Actuated g/C Ratio 0.54 0.54 0.13 0.72 0.18 0.18 v/c Ratio 0.08 0.61 0.56 0.40 0.51 0.56 Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9				Yes						
Actuated g/C Ratio 0.54 0.54 0.13 0.72 0.18 0.18 v/c Ratio 0.08 0.61 0.56 0.40 0.51 0.56 Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9						None		None		
v/c Ratio 0.08 0.61 0.56 0.40 0.51 0.56 Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9										
Control Delay 12.5 17.5 44.2 5.6 14.2 32.9 Queue Delay 0.0 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9										
Queue Delay 0.0 0.0 0.0 0.0 0.0 Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9										
Total Delay 12.5 17.5 44.2 5.6 14.2 32.9 LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9										
LOS B B D A B C Approach Delay 17.3 9.9 14.2 32.9	Queue Delay									
Approach Delay 17.3 9.9 14.2 32.9					5.6					
		В		D						
Approach LOS B A B C										
	Approach LOS		В		Α		В		С	

Intersection Summary

Cycle Length: 80

Actuated Cycle Length: 80

Offset: 0 (0%), Referenced to phase 2:EBTL and 6:WBT, Start of Green

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.61

Intersection Signal Delay: 14.0 Intersection LOS: B
Intersection Capacity Utilization 78.6% ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 1: Mill St & Guelph St



	۶	→	•	←	†	ļ
Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	22	603	125	1005	206	131
v/c Ratio	0.08	0.61	0.56	0.40	0.51	0.56
Control Delay	12.5	17.5	44.2	5.6	14.2	32.9
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	12.5	17.5	44.2	5.6	14.2	32.9
Queue Length 50th (m)	1.6	60.2	18.5	22.6	9.3	16.5
Queue Length 95th (m)	6.7	119.1	#46.2	58.1	23.3	27.8
Internal Link Dist (m)		244.8		229.4	42.0	68.3
Turn Bay Length (m)	40.0		50.0			
Base Capacity (vph)	282	996	225	2529	599	393
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.08	0.61	0.56	0.40	0.34	0.33
Intersection Summary						

⁹⁵th percentile volume exceeds capacity, queue may be longer. Queue shown is maximum after two cycles.

	۶	→	•	•	←	•	1	†	<i>></i>	/	↓	-√
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	ሻ	f)		ሻ	∱ ∱			4			4	
Traffic Volume (vph)	20	545	10	115	855	70	20	40	130	45	45	30
Future Volume (vph)	20	545	10	115	855	70	20	40	130	45	45	30
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width	3.3	3.6	3.6	3.3	3.6	3.6	3.6	3.6	3.6	3.6	3.6	3.6
Total Lost time (s)	4.0	4.0		4.0	4.0			4.0			4.0	
Lane Util. Factor	1.00	1.00		1.00	0.95			1.00			1.00	
Frpb, ped/bikes	1.00	1.00		1.00	1.00			0.98			0.99	
Flpb, ped/bikes	1.00	1.00		1.00	1.00			1.00			1.00	
Frt	1.00	1.00		1.00	0.99			0.91			0.97	
Flt Protected	0.95	1.00		0.95	1.00			0.99			0.98	
Satd. Flow (prot)	1741	1840		1728	3497			1660			1788	
Flt Permitted	0.29	1.00		0.95	1.00			0.96			0.66	
Satd. Flow (perm)	523	1840		1728	3497			1606			1209	
Peak-hour factor, PHF	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Adj. Flow (vph)	22	592	11	125	929	76	22	43	141	49	49	33
RTOR Reduction (vph)	0	0	0	0	5	0	0	116	0	0	18	0
Lane Group Flow (vph)	22	603	0	125	1000	0	0	90	0	0	113	0
Confl. Peds. (#/hr)	4		5	5		4	11		4	4		11
Heavy Vehicles (%)	0%	3%	0%	1%	2%	0%	0%	0%	2%	0%	0%	0%
Turn Type	Perm	NA		Prot	NA		custom	NA		custom	NA	
Protected Phases		2		1	6							
Permitted Phases	2						8	8		4	4	
Actuated Green, G (s)	40.3	40.3		9.9	54.7			12.3			12.3	
Effective Green, g (s)	43.3	43.3		10.4	57.7			14.3			14.3	
Actuated g/C Ratio	0.54	0.54		0.13	0.72			0.18			0.18	
Clearance Time (s)	7.0	7.0		4.5	7.0			6.0			6.0	
Vehicle Extension (s)	4.5	4.5		3.0	4.5			2.0			2.0	
Lane Grp Cap (vph)	283	995		224	2522			287			216	
v/s Ratio Prot		c0.33		c0.07	0.29							
v/s Ratio Perm	0.04							0.06			c0.09	
v/c Ratio	0.08	0.61		0.56	0.40			0.31			0.52	
Uniform Delay, d1	8.8	12.5		32.6	4.4			28.6			29.8	
Progression Factor	1.00	1.00		1.00	1.00			1.00			1.00	
Incremental Delay, d2	0.5	2.7		3.0	0.5			0.2			1.1	
Delay (s)	9.3	15.3		35.6	4.8			28.8			30.8	
Level of Service	А	В		D	А			С			С	
Approach Delay (s)		15.0			8.2			28.8			30.8	
Approach LOS		В			А			С			С	
Intersection Summary												
HCM 2000 Control Delay			13.7	H	CM 2000	Level of	Service		В			
HCM 2000 Volume to Capac	city ratio		0.60									
Actuated Cycle Length (s)	,		80.0	Sı	um of lost	time (s)			14.0			
Intersection Capacity Utilizat	tion		78.6%		:U Level o				D			
Analysis Period (min)			15									
c Critical Lane Group												

	٦	•	4	†	ļ	4
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	¥			4	î,	
Traffic Volume (veh/h)	15	35	40	65	70	30
Future Volume (Veh/h)	15	35	40	65	70	30
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	16	38	43	71	76	33
Pedestrians	7					
Lane Width (m)	3.6					
Walking Speed (m/s)	1.2					
Percent Blockage	1					
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				205		
pX, platoon unblocked						
vC, conflicting volume	256	100	116			
vC1, stage 1 conf vol						
vC2, stage 2 conf vol						
vCu, unblocked vol	256	100	116			
tC, single (s)	6.5	6.3	4.1			
tC, 2 stage (s)						
tF (s)	3.6	3.4	2.2			
p0 queue free %	98	96	97			
cM capacity (veh/h)	682	927	1477			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	54	114	109			
Volume Left	16	43	0			
Volume Right	38	0	33			
cSH	838	1477	1700			
Volume to Capacity	0.06	0.03	0.06			
Queue Length 95th (m)	1.7	0.7	0.0			
Control Delay (s)	9.6	3.0	0.0			
Lane LOS	7.0 A	3.0 A	0.0			
Approach Delay (s)	9.6	3.0	0.0			
Approach LOS	9.0 A	3.0	0.0			
•	A					
Intersection Summary						
Average Delay			3.1			
Intersection Capacity Utiliz	zation		22.3%	IC	CU Level c	of Service
Analysis Period (min)			15			

	۶	•	1	†	†	4
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations	W			ર્ન	f	
Traffic Volume (veh/h)	0	10	10	70	90	5
Future Volume (Veh/h)	0	10	10	70	90	5
Sign Control	Stop			Free	Free	
Grade	0%			0%	0%	
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	11	11	76	98	5
Pedestrians						
Lane Width (m)						
Walking Speed (m/s)						
Percent Blockage						
Right turn flare (veh)						
Median type				None	None	
Median storage veh)						
Upstream signal (m)				248		
pX, platoon unblocked				210		
vC, conflicting volume	198	100	103			
vC1, stage 1 conf vol	170	100	100			
vC2, stage 2 conf vol						
vCu, unblocked vol	198	100	103			
tC, single (s)	6.4	6.2	4.1			
tC, 2 stage (s)	0.1	0.2				
tF (s)	3.5	3.3	2.2			
p0 queue free %	100	99	99			
cM capacity (veh/h)	784	955	1489			
Direction, Lane #	EB 1	NB 1	SB 1			
Volume Total	11	87	103			
Volume Left	0	11	0			
Volume Right	11	0	5			
cSH	955	1489	1700			
Volume to Capacity	0.01	0.01	0.06			
Queue Length 95th (m)	0.3	0.2	0.0			
Control Delay (s)	8.8	1.0	0.0			
Lane LOS	А	Α				
Approach Delay (s)	8.8	1.0	0.0			
Approach LOS	А					
Intersection Summary						
Average Delay			0.9			
Intersection Capacity Utilization	ation		20.9%	10	CU Level o	of Sorvice
	allUH			IC	O LEVEL	n Service
Analysis Period (min)			15			